

4-22

4-071043

051053820000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 3-26-52

SW NW SE /4 SEC. 31, 13 S, 19 W
1650 feet from S section line
2310 feet from E section line

Operator license# 4694 Lease G.E. Riedel well # 2

Operator: Brock Oil & Gas Corporation County Ellis

Address: 25th & Vine - Ellner Bldg.#2 Well total depth 3888 feet ^{126.36}
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Ted Luebbers Surface pipe 8 5/8 Inch @ 645 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing - Rapid Well Sevice License#

Address: Russell, Kansas 67665 - Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 22 Month: April Year: 93

Plugging proposal received from: Ted Luebbers

Company: Brock Oil & Gas Corporation Phone: 913-628-1909

Were: 8 5/8" - 645' S.P. cwc. w/350 sx. cement. 5 1/2" casing set @
3884' w/175 sx. cement. Perf. 3878'. Casing squeezed @ 917' w/150 sx.
cement @ 1660' w/125 sx. cement - 860' w/100 sx. cement - 1498' - 1992'
with N/A. Proposal - order 350 sx. 65/35 pozmix - 10% gel. - 5 sx. hulls
Spot and displace all cement through tubing. Load both 5 1/2" casing
and 5 1/2" x 8 5/8" annulus with cement. Also perferate 5 1/2" casing
@ 2200'.

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 8:00P.M., Day: 22, Month: April, Year: 93

Actual plugging report: Brock ordered 350 sx. 65/35 pozmix - 10% gel. -
5 sx. hulls. Spotted and displaced all cement through tubing. Sq.annulus.

- 1) Casing squeezed perferated @ 2100' - 3 shots 120'.
- 2) 2 7/8" tubing @ 3750' w/150 sx. cement with 3 sx. hulls.
- 3) 2 7/8" tubing @ 1500' w/115 sx. cement with 1 sx. hulls. Cement
circulated out of 5 1/2" casing. 4) Squeezed 5 1/2" x 8 5/8" annulus
w/50 sx. cement - 400 P.S.I. 5) Filled 5 1/2" casing to surface with
20 sx. cement.

Remarks: Cemented by Allied Cement - Hays, Kansas

Condition of casing(in hole):GOOD BAD Anhy.plug: YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES NO

Plugged through TUBING , CASING . Elevation: GL

I did[]/did not[] observe the plugging.

Marion J. Schmidt
D.H.
(agent)
05-12-93
RCW

RECEIVED
STATE CORPORATION COMMISSION
MAY 12 1993
WICHITA, KANSAS

CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 5-14-93
INV. NO. 37703
4-22