

4-042041

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-00,608-0000

SW NE SE /4 SEC. 31, 13 S, 19 W
1650 feet from S section line
990 feet from E Section line

Operator license# 30606

322

Lease: Gus Riedel Well # 1

127.08

Operator: Murfin Drilling Company

County: Ellis

Address: 250 N. Water - Suite #300
Wichita, Kansas 67202

Well total depth 3910 feet
Conductor Pipe: inch @ feet
Surface Pipe: 10 3/4 Inch 1557 Feet
W/775 sxs cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Mike's Testing & Salvage - Allied Cementing License# -

Address: Chase, Kansas 67524

Company to plug at: Hour: 9:00 A.M. Day: 22 Month: March Year 2000

Plugging proposal received from: Monty

Company: Mike's Testing & Salvage Phone: -

Were: Ordered 500 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 400# hulls.
7" casing set at 3905' w/125 sxs cement. O.H. at 3905' - 3910'.

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 2:30 P.M., Day 22, Month: March, Year: 2000

Actual plugging report: Plug bottom with 50' sand and 7 sxs cement on sand. Shot casing at 3000' and rec. same. Pulled casing to 2100'. Spotted 300 sxs cement with 400# hulls, followed with 2 bbls water (H2O). Pulled to 1550'. Spotted 50 sxs cement, followed with 2 bbls water (H2O). Pulled to 900'. Spotted 50 sxs cement, followed with 2 bbls water (H2O). Pulled to 200' and circulated cement to surface - pulled casing with cement in cellar. Job complete.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING CASING: Elevation: G.L.

I did[X] / did not[] observe the plugging.

INVOICED 100
DATE 4/5/00
INV. NO. 061506

Dennis L Hamel
RECEIVED (agent)
STATE CORPORATION COMMISSION Form CP-2/3

APR 3 2000

CONSERVATION DIVISION
Wichita, Kansas

(R)

ALLIED CEMENTING CO., INC. 3757

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: R

15-051-00608-00-00

DATE <u>3/22/00</u>	SEC. <u>31</u>	TWP. <u>13 S</u>	RANGE <u>19 W</u>	CALLED OUT	ON LOCATION <u>9:00 AM</u>	JOB START <u>9:45 AM</u>	JOB FINISH <u>2:00 PM</u>
LEAS. <u>B Riedel</u>		WELL # <u>1</u>	LOCATION <u>Navy Golf Course</u>		COUNTY <u>Ellis</u>	STATE <u>Ks</u>	
OLD OR NEW (Circle one)			<u>Rd 7W 12S 14W 4S</u>				

CONTRACTOR Mike Testin & Salvage OWNER _____
 TYPE OF JOB plug to abandon
 HOLE SIZE _____ T.D. _____
 CASING SIZE 7" DEPTH _____
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX _____ MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT _____

CEMENT AMOUNT ORDERED 500 @ 10% gel
4 Halls
used 470

COMMON	<u>282</u>	@	<u>6.35</u>	<u>1790.70</u>
POZMIX	<u>188</u>	@	<u>3.25</u>	<u>611.00</u>
GEL	<u>32</u>	@	<u>9.50</u>	<u>304.00</u>
CHLORIDE		@		
<u>Halls</u>	<u>4</u>	@	<u>15.50</u>	<u>62.00</u>
		@		
		@		
		@		
		@		
HANDLING		@	<u>1.05</u>	<u>525.00</u>
MILEAGE	<u>4 1/2</u>	/mile		<u>180.00</u>
TOTAL				<u>3472.70</u>

EQUIPMENT

153
 PUMP TRUCK CEMENTER paul
 # _____ HELPER _____
 BULK TRUCK DRIVER Jason
 # 213 DRIVER _____
 BULK TRUCK DRIVER Dave
 # 160 DRIVER _____

REMARKS:

Spent 300 sk & 4 Halls @ 2150 pulled to 1500
Spent 50 sk pulled to 900
Spent 120 sk pulled to 230 mixed 100 sk & cir & filled cellar

SERVICE

DEPTH OF JOB				
PUMP TRUCK CHARGE			<u>450.00</u>	
EXTRA FOOTAGE		@		
MILEAGE	<u>9</u>	@	<u>3.00</u> <u>27.00</u>	
PLUG		@		
		@		
		@		
TOTAL				<u>477.00</u>

RECEIVED
STATE CORPORATION COMMISSION

APR 24 2000

CHARGE TO: Martin
 STREET _____
 CITY _____ STATE _____ ZIP _____

CONSERVATION DIVISION
Wichita, Kansas

FLOAT EQUIPMENT

	@	
	@	
	@	
	@	
	@	

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]

TOTAL _____
 TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS
 PRINTED NAME N. J. Andrews