

4- 062652

6-16

68
R

OST-19210-00-00

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 7-1-59

SW NE NE /4 SEC. 12, 13 S, 18 W
4290 feet from S section line
990 feet from E section line

Operator license# 5145

Lease Staab Pratt well # A-1

Operator: Dreiling Oil, Inc.

County Ellis

Address: Box 1000
Victoria, Kansas 67671

Well total depth 3637 feet ^{118.2⁰}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 150 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Dreiling Oil, Inc. License# 5145

Address: Box 1000, Victoria, Kansas 67671

Company to plug at: Hour: 9:00A.M. Day: 16 Month: June Year: 92

Plugging proposal received from: Ivan R. Edsall

Company: Dreiling Oil, Inc. Phone: 913-735-2204

Were: Order 300 sks. of 60/40 posmix - 8% gel. - 5 sks. hulls.

Plugging Proposal Received by: Gilbert G. Scheck

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 10:00A.M. Day: 16 , Month: June , Year: 92

Actual plugging report: 8 5/8" @ 150' w/110 sks. 5 1/2" @ 3599' w/200
sk. Top perf. @ 3366'. Plugged bottom with sand and 5 sks. cement to
3402'. Pump in 5 1/2" casing 25 sks. cement followed with 5 sks. hulls
in 250 sks. cement with 300 P.S.I.

Max. pressure on 5 1/2" - 300 P.S.I. Shut in @ 300 P.S.I.

Max. pressure on backside - 250 P.S.I. Shut in @ 250 P.S.I.

Total sacks 300 cement.

Remarks: D.V. from 1340' with 350 sks.

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES 1400 NO COMMISSION

Bottom plug(in place): YES X , CALC , NO Dakota plug: YES X , NO

Plugged through TUBING , CASING X . Elevation: 2100 GL 4 1992

I did [X] / did not [] observe the plugging.

Gilbert G. Scheck 06-24-92
Wichita, Kansas

(agent)

Form CP-2/3

DATE 7-2-92

INV. NO. 35608

INVOICED