

4-071159

051-05563-0990

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-~~10-18-50~~

12-19

SW NE SE /4 SEC. 26, 11 S, 17 W
1650 feet from S section line
990 feet from E section line

Operator license# 5447

Lease: McCord "A" Well # 14

Operator: OXY USA, Inc.

County: Ellis

Address: 110 S. Main - Suite #800
Wichita, Kansas 67202
J.D. Hininger

Well total depth 3656 ^{118.82} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 1290 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Cement Company License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 19 Month: December Year: 1995

Plugging proposal received from: Gary Wagoner

Company: OXY USA, Inc. Phone: 913-434-7681

Were: 8 5/8"-1290' S.P. cwc. w/600 sxs cement. 5 1/2" casing set at 3656' w/160 sxs cement. P.B.T.D. 2490'. Perfs 2462'. 5 1/2" casing squeeze at 2515' w/120 sxs cement and at 2480' w/270 sxs cement. Proposal - 350 sxs 60/40 pozmix - 10% gel and 5 sxs hulls. Pump in 5 1/2" casing with pump truck. Load 5 1/2" casing from top to bottom - circulate cement out of 5 1/2" x 8 5/8" annulus. Shut in under pressure.

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All , Part , None

Completed: Hour: 11:30 A.M. Day: 19 Month: December Year: 1995

Actual plugging report: OXY USA, Inc. ordered 350 sxs 60/40 pozmix - 10% gel and 5 sxs hulls. Pumped in with pump truck.

- 1) Perforated 5 1/2" casing at 1325' and 1925'.
- 2) Pumped in 5 1/2" casing (annulus open) with 10 sxs cement followed with 290 sxs cement with 5 sxs hulls added. Cement circulated out of 5 1/2" x 8 5/8" annulus.
- 3) Shut in and squeezed 5 1/2" casing. Max. P.S.I. 850#. S.I.P. at 350#.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Cemented by Halliburton Cement Company.

DEC 26 1995
12-26-95
RCW

Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES X , NO

Plugged through: TUBING , CASING . Elevation: _____ GL

I did / did not observe the plugging.

Marion J. Schmidt
(agent)

INVOICED

DATE JAN 09 1996

INV. NO. 4445-7

12-19 FEB 29 1996