

4-071160

OSI-05560-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-07-03-41

SE NE SE /4 SEC. 26, 11 S, 17 W
1700 feet from S section line
330 feet from E section line

12-19

Operator license# 5447

Lease: McCord "A" Well # 10

Operator: OXY USA, Inc.

County: Ellis

Address: 110 S. Main - Suite #800
Wichita, Kansas 67202
J.D. Hininger

Well total depth: 3654 118.76 feet
Conductor Pipe: 12 1/2 inch @ 66 0 feet
Surface pipe 8 5/8 Inch @ 360 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Cement Company License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 19 Month: December Year: 1995

Plugging proposal received from: Gary Wagoner

Company: OXY USA, Inc. Phone: 913-434-7681

Were: 12 1/2" conductor 66' cwc. w/175 sxs. 8 5/8" S.P. - 360' cwc. w/175 sxs cement.
5 1/2" casing set at 3553' w/100 sxs cement. C.I.B.P. at 3470'. Perfs at 3359' - 3445'.
5 1/2" casing squeeze at 410' w/229 sxs cement at 763' w/650 sxs cement. Proposal - 325 sxs
60/40 pozmix - 10% gel and 5 sxs hulls. Perforate 5 1/2" casing at 1325' and 1975'. Pump
in casing with pump truck. Load all casing and annulus into cement from top to bottom. Shut
in under pressure.

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All , Part , None

Completed: Hour: 10:00 A.M. Day: 19 Month: December Year: 1995

Actual plugging report: OXY USA, Inc. ordered 325 sxs 60/40 pozmix - 10% gel and 5 sxs hulls.
Pumped in with pump truck. 5 1/2" casing was squeezed with 650 sxs cement.
1) Perforated 5 1/2" casing at 1325' and 1925'.
2) Pumped in 5 1/2" casing with 10 sxs cement followed with 225 sxs cement with 5 sxs hulls
added. Max. P.S.I. 1000#. S.I.P. 350#.
3) Squeezed 8 5/8" x 5 1/2" annulus, would not take cement. Max. P.S.I. 500#. S.I.P. 500#.
12 1/2" x 8 5/8" annulus 66' - cement visable at surface.

Remarks: Cemented by Halliburton Cement Company.

Condition of casing(in hole): GOOD BAD Any plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL

I did / did not observe the plugging.

INVOICED

DATE JAN 09 1996

INV. NO. 44456

12-19 FEB 29 1996

RECEIVED STATE CORPORATION COMMISSION 12-26-95

Signature of Marion J. Schmidt (agent)
Form CP-2/3

OKHD.