

4-28 4-041897

API Number: 15-051-05905-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

SW NW SE /4 SEC. 26, 11 S, 17 W
1650 feet from S section line
2310 feet from E section line

Operator license# 5447

Lease: McCord "A" Well # 7

Operator: OXY USA, Inc.

County: Ellis 117.20

Address: P.O. Box 300
Tulsa, OK 74102-0300

Well total depth 3606 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 3/4 Inch @ 1109 feet
w/ 365 sxs.cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00A.M. Day: 28 Month: April Year 1997

Plugging proposal received from: Gary Wagner

Company: OXY USA, Inc. Phone:

Were: 5 1/2" casing set at 3542' w/100 sxs cement. O.H. 3606'. Dakota at 700'. W.L.M. 3551'. Squeeze at 1116' w/100 sxs cement.
Ordered 300 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 400# hulls.

RECEIVED
KANSAS CORP. COMM
MAY 22 A 12:58
05-22-97

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 11:15 P.M., Day: 28, Month: April, Year: 1997

Actual plugging report: 5 1/2" casing. Squeezed 25 sxs cement with 100# hulls, followed with 10 sxs gel, followed with 200 sxs cement w/300# hulls. Max. P.S.I. 1200#. S.I.P. 800#. 8 5/8" S.P. Pressured-up to 600# - no cement.

Remarks: Checked cement on May 1, 1997 - OK. Filled to surface with 20 sxs.
Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES X, CALC, NO
Plugged through TUBING, CASING X
Anhy.plug: YES X NO
Dakota plug: YES X, NO
Elevations: G.L.

I did [X] / did not [] observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED

DATE 5-22-97

INV. NO. 48165

4-28