

4-28

4-041893

keep

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-05-1-03452-00-00

SWSONW

~~NW SW~~ /4 SEC. 26, 11 S, 17 W  
2317 feet from ~~N~~ section line  
330 feet from W section line

Operator license# 5447

Lease: Hall B Well # 5

Operator: OXY USA, Inc.

County: Ellis 111.05

Address: P.O. Box 300  
Tulsa, OK 74102-0300

Well total depth 3417 feet  
Conductor Pipe: 15 1/2 inch @ 130 feet  
Surface pipe 10 3/4 Inch @ 1150 feet  
w/ 400 sxs.cmt.

Aband. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00A.M. Day: 28 Month: April Year 1997

Plugging proposal received from: Gary Wagner

Company: OXY USA, Inc. Phone: \_\_\_\_\_

Were: 7" casing set at 3411' w/250 sxs cement. O.H. at 3417'. T.O.F. 980'. Perf at 130'-1100'.  
Ordered 450 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls - 40 sxs gel.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[ ], Part[ X ], None[ ]

Completed: Hour: 9:45 A.M., Day: 28, Month: April, Year: 1997

Actual plugging report: 7" casing. Mixed and squeezed 100 sxs cement with 300# hulls, followed with 40 sxs gel, followed with 290 sxs cement with 200# hulls. Max. P.S.I. 500#. S.I.P. 300#. 10 3/4" S.P. Squeezed 35 sxs cement at 500#, and S.I.P. at 300#. 15 1/2" conductor pipe - cement at surface.

Remarks: Checked cement on May 1, 1997 - OK.

Condition of casing(in hole): GOOD  BAD \_\_\_\_\_ Any plug: YES  NO \_\_\_\_\_  
Bottom plug(in place): YES , CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES , NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING . Elevation: \_\_\_\_\_ G.L.

I did[  ] / did not[ ] observe the plugging.

*Dennis L Hamel*  
(agent)

Form CP-2/3

INVOICED

DATE 5-22-97

INVOICE # 48164

4-28

RECEIVED  
KANSAS CORP COMM  
MAY 22 1997  
05-22-97