

LEASE NAME McCord "A"

WELL NUMBER 14

1650 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 26 TWP. 11S RGE. 17W (E) or (W)

COUNTY Ellis

Date Well Completed 12-8-50

Plugging Commenced 12-22-96

Plugging Completed 12-22-96

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Oxy USA Inc.

ADDRESS 110 S. Main #800 Wichita, KS 67002

PHONE# (316) 265-5624 OPERATORS LICENSE NO. 5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/26/95 (date)

by Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes, Plugging Application Form

Producing Formation Neva Depth to Top 2462 Bottom 2464 T.D. 3656'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	1290'	8 5/8"	1290'	0'
		0	3656'	5 1/2"	3656'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Perforated 5 1/2" casing at 1325' and 1925'. Pumped 325 sk of 60/40 pozmix cement with 10% gel + 450# cottonseed hulls. Cement circulated to surface. Shut casing in w/ 300 psi. Pressured 8-5/8" to 300 psi - held OK.

Name of Plugging Contractor Halliburton

Address Hays, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Timothy J. Voss

(Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Timothy J. Voss


(Address) 110 S. Main #800 Wichita, KS 67002

SUBSCRIBED AND SWORN TO before me this 8th day of March, 19 96

Liz Heibel

Notary Public

My Commission Expires: 2/22/96



RECEIVED
 KANSAS CORPORATION COMMISSION
 License No. _____

MAR 17 1996

03-11-96
 CONSERVATION DIVISION
 WICHITA, KS