

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Ellis

County. Sec. 26 Twp. 11 Rge. (E) 17 (W)

Location as "NE/CNW%SW%" or footage from lines Center of NW NW NW

Lease Owner Cities Service Oil Co.

Lease Name Hall "B" Well No. 1

Office Address Bartlesville, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 11/15/37 19

Application for plugging filed 3/23/54 19

Application for plugging approved 3/24/54 19


Plugging commenced 3/23/54 19

Plugging completed 3/24/54 19

Reason for abandonment of well or producing formation non-commercial

If a producing well is abandoned, date of last production 3/17/54 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty

Producing formation Arbuckle Depth to top 3380 Bottom _____ Total Depth of Well 3383 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				15 1/2	104	0
				10-3/4	1114	0
				7	3380	2578

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill with sand to 3340', dump five sx. cement, mud hole to 310'
dump 10' rock bridge, 25 sx. cement, mud to 35', 5' rock bridge,
10 sx. cement to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Schull Casing Pulling Co.

Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF Russell, ss.

Roy J. Turner (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Roy J. Turner

(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of April, 1954

My commission expires July 26, 1954

John A. Berg
STATE CORPORATION COMMISSION Notary Public.

PLUGGING
FILE SEC 26 T 11 R 17
BOOK PAGE 22 LINE 13

MAY 4 - 1954
05-04-54
CONSERVATION DIVISION
Wichita, Kansas

WELL RECORD

Company Cities Service Oil Co. Well No. 1 Farm Hall "B"
 Location 330' S. & 330' E. of NW Cor. Sec. 26 T. 11 R. 17W
 Elevation _____ County Ellis State Kansas
 Drlg. Comm. October 10, 1937 Contractor Corbett & Barbour
 Drlg. Comp. November 13, 1937 Acid None
 T. D. 3399' Initial Prod. 1866 oil, 0 water, 24 hrs. natural

CASING RECORD:

15-1/2" 104' cem. 104 sacks
 10-3/4" 1114' cem. 400 sacks
 7" 3380' cem. 250 sacks

40'1" of 5-3/16" liner at 3388'; liner has cave catcher at 3380 1/2' and perfs. from 3380 1/2' to 3382'.

surface	104
shale & shells	800
red rock	840
red beds & shale	1075
red beds	1114
anhydrite	1165
red beds	1380
shale & shells	1460
shale & salt	1500
salt	1600
shale & shells	1760
lime	1845
shale & shells	1974
shale & broken lime	2070
lime	2178
shale & broken lime	2250
broken lime	2317
shale & lime	2411
shale	2440
lime	2477
lime & shale	2573
shale & shells	2705
lime & shale	2772
shale & shells	2832
shale	2835
lime Topeka	2903
lime	3000
shale & shells	3004
lime (stain 3055-87)	3087
lime - cored	3093
SLM Corr. 3093=3089	
lime	3103
broken lime & shale	3114

lime	3127
shale	3145
Kansas City lime	3153
broken lime	3179
SLM Corr. 3179=3189	
shale - cored	3194
broken lime & shale	3230
broken lime	3275
lime & shale	3311
chert & shale	3344
lime	3367
broken lime & shale	3381
shale - cored	3382
lime - cored	3386
shale - cored	3388
shaly sand - cored	3390
shale - cored	3393
lime - cored	3394
SLM Corr. 3394=3381	
lime	3399
Top Arbuckle	3380'
Penetration	19'
Total Depth	3399'

SYFO: 1000' OK
 1250' 1°
 2000' 1°
 2250' 1°
 2750' OK

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 24 1954
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 26 T 11 R 17W
 BOOK PAGE 22 LINE 13