

15-051-05414-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

Drilling
API NUMBER Completed 8-19-53
LEASE NAME Hall "B"
WELL NUMBER 24
SPOT LOCATION 825'S - 405'W
SEC. 26 TWP. 11 RGE. 17 ~~R&X(W)~~
COUNTY Ellis
Date Well Completed 8-19-53
Plugging Commenced 5-8-84
Plugging Completed 5-8-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Cities Service Oil and Gas Corporation
ADDRESS 800 Sutton Place, Wichita, Ks. 67202

PHONE # (316) 265-5624 OPERATORS LICENSE NO. 5447

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #6

Is ACO-1 filed? Well Completed 8-19-53 If not, is well log attached? Yes

Producing formation Arbuckle Depth to top 3552' bottom 3556' T.D. 3556'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	1230'	- 0 -
				5 1/2"	3552'	- 0 -

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Plugged w/30 sacks 50/50 Pozmix w/8% gel and 3% CaCl-2, 1/4 lb. Flo-seal, 4 sacks hulls, 14 sacks gel as follows: pumped down 5 1/2" casing w/25 sacks cement, 14 sacks gel, 1 - 1/2 sacks hulls, 135 sacks cement. Plug and abandonment completed May 8, 1984. State witness - Dennis Hemei

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. _____
Address 1100 E. 8th, Hays, Kansas 67601

STATE OF Kansas COUNTY OF Sedgwick, ss.

Charles N. Richmond (employee of operator) ~~xxx~~
(~~xxxxxxx~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.)
(Signature) Charles N. Richmond
(Address) 800 Sutton Place, Wichita, Ks. 67202

SUBSCRIBED AND SWORN TO before me this 1 day of June, 1984

JACQUELINE PIERCE
NOTARY PUBLIC
STATE OF KANSAS
My Appointment Expires:
2-27-85

Jacqueline Pierce
Notary Public
Jacqueline Pierce

RECEIVED
STATE CORPORATION COMMISSION
JUN 06 1984
CONSERVATION DIVISION
Wichita, Kansas

WELL RECORD

15-051-05414-0000

Company Cities Service Oil Co. Well No. 24 Farm Hall "B"
 Location 825' South and 405' West of Center Sec. 26 T. 11 R. 17W
 Elevation 2033 (2030 Gr.) County Ellis State Kansas
 Drlg. Comm. July 26, 1953 Contractor Glenn R. Nye Drilling Co.
 Drlg. Comp. August 19, 1953 Acid 250 gals. 8-22-53 ✓
 T. D. 3556' Initial Prod. 55 oil, 67 water, 24 hrs. (8-24-53)

CASING RECORD:

8-5/8" @ 1230' cem. 300 ex cement and
 75 ex Stratacrete
 5-1/2" @ 3552' cem. 175 ex cement

FORMATION RECORD:

shale	0-455
sand	500
shale & sand	850
red bed & shale	1214
anhydrite	1248
shale & shells	1800
shale & lime	1915
lime & shale	3495
sand & shale	3520
lime	3554
lime	3554 RTD = 3552 SLM
	3556 T. D.

Corr. Heebner	3177'
Corr. Dodge	3200'
Corr. Lansing	3229'
Corr. Simpson	3485'
Corr. Artuckle	3518' (+1485)
Penetration	38'
Total Depth	3556'

85 gals. oil in 1 hr.
 94' oil in 1 hr.
 213' oil in 3 hrs.
 344' oil in 7 hrs.
 425' oil in 9 hrs.
 509' oil in 11 hrs.

SLOPE TESTS (SHURE SHOT):

1000'	1°
1500'	1°
2000'	1°
2500'	3/4°
3000'	1°

7-7/8" rotary hole.

RECEIVED
STATE CORPORATION COMMISSION

FEB 15 1984

CONSERVATION DIVISION
Wichita, Kansas