

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec. 26 Twp. 11S Rge. (E) 17(W)

Location as "NE/CNW/SW" or footage from lines 915' FNL 990' FEL

Lease Owner Cities Service Oil Company

Lease Name McCord Well No. 15

Office Address Box 553 Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed Jan. 19 51

Application for plugging filed 9-20 19 68

Application for plugging approved 9-23 19 68


Plugging commenced 10-2 19 68

Plugging completed 10-2 19 68

Reason for abandonment of well or producing formation Non-economical

If a producing well is abandoned, date of last production May 10 19 68

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Leo Massey Hays, Kansas

Producing formation LKC Depth to top 3467 Bottom 3717 Total Depth of Well 3650 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	316'	None
				5 1/2"	3650'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped 5 Sx. hulls; 25 sx. Cement; 35 Sx. Gell; 5 1/2" plug;

75 Sx. 50/50 Pozmix. Pump pressure 250# Casing filled

S.I. pressure 200#. Cut off casing and welded on cap.

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Company

Address Hays, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.

M. M. Hardin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M.M. Hardin M.M. Hardin, Dist. Supt.


Box 553 Russell, Kansas 67665

(Address)

SWORN to before me this 11th day of October, 19 68

10-5-72

James F. Kyger Notary Public.



WELL RECORD

15-051-05564-0000

Company Cities Service Oil Company Well No. 15 Farm McCord
 Location 915' South and 990' West of NE Corner Sec. 26 T. 11 R. 17W
 Elevation 2087 (2085 Gr.) County Ellis State Kansas
 Drlg. Comm. November 7, 1950 Contractor Holm Drilling Company
 Drlg. Comp. November 18, 1950 Acid 250 gals. 3613-19 (12-30-50)
 T. D. 3650' Initial Prod. Physical Potential: 14 oil, 72% water, 24 hrs. (1-25-51)
 P.B.T.D. 3644'

CASING RECORD:

8-5/8" @ 316' cem. 200 sx cement
 5-1/2" @ 3650' cem. 150 sx cement
 DV @ 1277' w/ 400 sx.

FORMATION RECORD:

lime	0-75
shale & shells	316
shale	375
shale & shells	500
shale, shells & sand	900
sand, shale & shells	965
red bed	1265
anhydrite	1302
shale & shells	1685
salt, shale & shells	1800
shale & shells	2095
lime & shale	2285
shale & lime	2355
lime & shale	2555
shale & lime	2630
shale & shells	2950
shale & lime	3010
lime	3650

3650 RTD = 3650 SLM

Top Lansing	3287'
Top Simpson Shale	3548'
Top Erosional Arbuckle	3557'
Top Arbuckle	3560'
Penetration	90'
Total Depth	3650'

Drilled cement to 3644' S. L. M.

Perf. 22 shots 3613-19

130' oil, trace water, 13-1/2 hrs.

SYFC:	500'	0°
	1000'	0°
	1500'	0°
	2000'	1°
	2500'	0°
	3000'	0°

7-7/8" rotary hole.

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 23 1968
 CONSERVATION DIVISION
 Wichita, Kansas