

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-057-30655-0000
WELL PLUGGING RECORD

Ellis County, Sec. 6 Twp. 13S Rge. 20 (X) (W)

Location as "NE/CNWxSWx" or footage from lines C-W/2-NW-NE

Lease Owner SUNRAY OIL CORPORATION

Lease Name Bittel B Well No. 3

Office Address Box 195, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed October 26 19 53

Application for plugging filed June 26 19 53

Application for plugging approved June 29 19 53

Plugging commenced August 14 19 53


Plugging completed August 14 19 53

Reason for abandonment of well or producing formation Arbuckle depleted.

No oil in Marmaton formation.

If a producing well is abandoned, date of last production February 3 19 52

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation Marmaton Depth to top 3777 Bottom 3814 Total Depth of Well PB 3805 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Marmaton	Water	3778	3798	10	119	none
Arbuckle	Oil - depleted	3832	3846	7	3827	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Total depth 3846' in Arbuckle. Plugged back to 3805 with Baker plug and 20 sax cement to 3705'. Mudded hole to 150', placed 30 sax cement to surface. Well plugged under supervision of Eldon Petty, Hays, Kansas.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sunray Oil Corporation

Address Box 195, Great Bend, Kansas

STATE OF KANSAS COUNTY OF BARTON

Robert K. Crouch (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert K. Crouch

Box 195, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of September, 19 53

My commission expires December 24, 1956

24-2675-S 2-52-20M



PLUGGING
FILE SEC 6 T 13 R 20W
BOOK PAGE 110 LINE 41

RECEIVED
STATE CORPORATION COMMISSION
9-4-53
SEP - 4 1953
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

Sunray Oil Corporation, #3Bittel 'B'
C-W/2-NW-NE, Section 6-13S-20W
Ellis County, Kansas

CONTRACTOR: Patton Drilling Company
Drilling Commenced: October 5, 1943
Drilling Completed: October 26, 1943

15.05/30655.00.00

Casing - 10" 119'
7" 3830'

Clay	8
Shale, sand, line	110
Lime	119
Shale & Shells	865
Lime Brkn	885
Shale & Shells	1015
Sand	1240
Red bed	1530
Anhydrite	1535
Lime & anhydrite	1565
Shale	1700
Shale & Shells	1925
Salt	2045
Shale	2100
Lime & Shale, brkn	2140
Lime & Shale	2250
Shale & Shells	2335
Shale	2408
Shale & Shells	2516
Lime & Shale	2730
Shale	2850
Lime & Shale	2950
Shale	3060
Lime & Shale	3320
Lime	3350
Lime & Shale	3385
Lime	3405
Lime & Shale	3462
Lime	3565
Lime & Shale	3638
Lime	3672
Lime & Shale	3739
Shale	3777
Chert & Lime	3814
Lime	3830
Lime Arbuckle	3832
Total Depth	3847

I, Robert K. Crouch hereby certify the above to be a true and complete copy of the driller's log for Bittel 'B' #3, C-W/2-NW-NE, Section 6-13S-20W, Ellis County, Kansas.

Robert K. Crouch

Subscribed and sworn to before me this 3rd day of September, 1953.

W. C. ...
Notary Public

My Commission Expires: December 24, 1956

FILE 306-113-206
110-1241

RECEIVED
STATE OF KANSAS COMMISSION
OCT 10 1953
DIVISION
Wichita, Kansas