

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Ellis County, Sec. 6 Twp. 13S Rge. 20W XXXXXXXX

Location as "NE/CNW/SW" or footage from lines C W/2 NE/1 NE/1

Lease Owner Sunray Mid-Continent Oil Company

Lease Name Bittel B Well No. 4

Office Address Box 195, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Salt Water Disposal

Date well completed June 5 1945

Application for plugging filed August 4 1955

Application for plugging approved August 8 1955

Plugging commenced August 5 1955

Plugging completed August 5 1955

Reason for abandonment of well or producing formation Well was used as salt water disposal, unable to take water.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 4059 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pumped down casing 1 1/2" Pozmix cement with 200# pressure. Started 8-5/8" plug-in casing. Pumped 1 1/2" Pozmix cement down 8 5/8" casing with 350 to 450# pressure. Plug pumped down to 500', filled cement to surface, closed casing.

Well log attached.

RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1955
9-21-55
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton OilWell Cementing Company

Address Great Bend, Kansas


STATE OF Kansas, COUNTY OF Barton, ss.

Norman E. Montgomery (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Norman E. Montgomery

Box 195, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 16th day of September, 1955



Notary Public

PLUGGING
FILED SEC 6 T 13 R 20W
BOOK PAGE 41 LINE 11

RECEIVED
STATE CORPORATION COMMISSION
SEP 17 1955
CONSERVATION DIVISION
Wichita, Kansas

COPY COPY COPY COPY

Sunray Oil Corporation
Tulsa, Oklahoma

NE/4 6-13-20
Ellis County, Kansas

Bittel B # 4

Contractor: Parker Drilling Co.
Commenced: 2-9-45
Completed: 3-4-45

soil & sand	0-70	
shale & shells	70-540	
sand & shale	540-790	
shale & lime	790-855	
shale & shells	855-1000	
sand & shells	1000-1225	
shale & shells	1225-1435	
red bed & shale	1435-1507	
anhydrite	1507-1555	8 5/8" set @ 1512'
red bed	1555-1735	cem w/400 sax
shale & shells	1735-2190	
lime & shale	2190-2320	
lime	2320-3734	
cherty lime	3734-3739	
lime	3739-3749	
cherty lime	3749-3782	
congl. & shale	3782-3801	
shale & sand	3801-3828	
lime	3828-3854	
dolomite sand	3854-3865	
lime	3865-4035	
sand & granite	4035-4059	TD

County of Barton) ss
State Of Kansas)

I, Ferd Sabourin, do swear this is a true and correct log of the Bittel B #4 well.

s/ F. Sabourin

Sworn to and subscribed before me this 4th day of May, 1945.

s/ Virginia Schraeder
NOTARY PUBLIC

MY COMMISSION EXPIRES FEB. 14, 1949

PLUGGING
 FILE SEC 6 T 13 R 20W
 BOOK PAGE 141 LINE 11