

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas. 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-051-20047-0000

API NUMBER 4-25-67

LEASE NAME Clem Bittel

WELL NUMBER #3

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

Approx.
2970 Ft. from S Section Line

Approx.
1650 Ft. from E Section Line

SEC. 6 TWP. 13S RGE. 20 (N or W)

COUNTY Ellis

Date Well Completed 4-25-67

Plugging Commenced 3-7-86

Plugging Completed 3-7-86

LEASE OPERATOR Rains & Williamson Oil Co. Inc.

ADDRESS 435 Page Court, 220 West Douglas, Wichita, Kan. 67202

PHONE# (316) 265-9686 OPERATORS LICENSE NO. 5146

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3836 Bottom 3840 T.D. 3840

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Arbuckle</u>	<u>3836 - 3840</u>			<u>5 1/2</u>	<u>3837</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

B-J Titan, Pumped down 2 1/2 tubing into 5 1/2 with 100 sk. cement 60/40 poz mix 6% gel with 3 sk. hulls, pulled out 33 joints of tubing, pumped down tubing with 100 sk. cement with 1 sk hulle, pulled out 32 joints of tubing, pumped down tubing with 100 sk. cement 4/1 sk. allo flake and 1 sk hulle, well on vacuum, pumped another 80 sk. cement with 1 sk cello.

(If additional description is necessary, use BACK of this form.) (over)

Name of Plugging Contractor Paul Stephens License No. 683

Address P.O. Box 166

STATE OF Kansas COUNTY OF Pratt, ss.

Rains & Williamson Oil Co. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Paul Stephens

(Address) _____

SUBSCRIBED AND SWORN TO before me this 11th day of March, 19 86

Mary Alice Rupp
Notary Public

My Commission Expires: _____

Mary Alice Rupp
NOTARY PUBLIC
State of Kansas
MY COM. EXPIRES 2-29-88

RECEIVED
STATE CORPORATION COMMISSION

MAR 13 1986
3-13-86

Form CP-4
Revised 08-84

Poker and 1/2 sk. hulls, circulated to top, pulled find 28 joints of tubing topped off 5 1/2 with 25 sk. cement. Max. press. 600 lbs. Shut in at 200 lbs. Down 8 5/8 with 100 sk. cement 10/40 po2 mix 6% gel w/ 2 sk. hulls. Max. press. 600 lbs. Shut in at 200 lbs. Plugged down at 4:40 P.M. State agent Marion Schmidt.

W. J. ...
advises ...
call ...
(2000)

11
MAR 1 3 1960

MAR 1 3 1960
MAR 1 3 1960