

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-30176-

LEASE NAME CLEM BITTEL

WELL NUMBER #1

SPOT LOCATION SW SW NE

SEC. 6 TWP. 13 SRGE. 20 ~~XX~~ or (W)

COUNTY Ellis

Date Well Completed 11-5-65

Plugging Commenced 5-29-85

Plugging Completed 5-29-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Rains & Williamson Oil Co., Inc.

ADDRESS 435 Page Ct., 220 W. Douglas, Wichita, KS 67202

PHONE # (316) 265-9686 OPERATORS LICENSE NO. 5146

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #6 1014 Cody Hays, Kansas 67601

Is ACO-1 filed? If not, is well log attached?

Producing formation Conglomerate Depth to top bottom T.D. 3837

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	225'	None
				5 1/2"	3834'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.
Cemented with 50 sx. 50-50 poz., 28 sx. gel, 3 sx. hulls down on 5 1/2" casing. Dropped Plug.
Cemented with 100 sx. 50-50 poz., 1 sx. hulls tied on to 8 5/8" cemented with 5 sx. 50-50 poz.
Pressured up to 500# tied back on to 8 5/8" cemented with 145 sx. 50-50 poz. Closed in
Pressure 150#. Plugged @ 11:20 a.m. 5-29-85. State Plugger Dale Balthazor.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc. License No. 682
Address 435 Page Court, 220 West Douglas, Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Sedgwick, ss.

JUN 25 1985


Wilson Rains, President of Rains & Williamson Oil (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

CONSERVATION DIVISION
Wichita, Kansas

(Signature) Wilson Rains
WILSON RAINS, PRESIDENT
(Address) 435 Page Ct., 220 West Douglas
Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 21st day of June, 19 85

Juanita M. Green
Notary Public
Juanita M. Green



My Commission expires: 10-4-87