

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-051-30070-0000  
5-7-65

LEASE NAME Bittel "A"

WELL NUMBER 1

2310 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 6 TWP. 13 RGE. 20 ~~W~~ or (W)

COUNTY Ellis

Date Well Completed 5-7-65

Plugging Commenced 8-1-89

Plugging Completed 8-1-89

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Glenn D. Diehl Oil Operations

ADDRESS P. O. Box 234, Hays, KS 67601

PHONE# (913) 625-6711 OPERATORS LICENSE NO. 9346

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 12, 1989 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation Arbuckle Depth to Top 3830 Bottom 3838 T.D. 3838

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	230	8-5/8"	230'	-0-
		0	3830	5 1/2"	3830'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped 225 sacks 65/35 poz 10 % gel with 5 sacks hulls down casing @ 1000#. Shut in casing @ 400#. Pumped 65 sacks 65/35 poz 10% gel down backside @ 350#, shut in backside @ 150#

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. RECEIVED

Address 1100 East 8th St., Hays, KS 67601 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Glenn D. Diehl Oil Operations AUG 11 1989


STATE OF Kansas COUNTY OF Ellis, ss. CONSERVATION DIVISION  
Wichita, Kansas

Glenn D. Diehl (Signature) (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Glenn D. Diehl

(Address) P. O. Box 234, Hays, KS 67601



SUBSCRIBED AND SWORN TO before me this 8th day of August, 19 89

Robert E. Diehl  
Notary Public

My Commission Expires: 8-27-89