

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 100 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-051-30318-00-00

API NUMBER 4-1-86

LEASE NAME E. B. H-1

WELL NUMBER #4

Approx. 2970 Ft. from S Section Line

Approx. 3960 Ft. from E Section Line

SEC. 6 TWP. 13S RGE. 20 (E or W)

COUNTY Ellis

Date Well Completed 4-1-86

Plugging Commenced 2-20-86

Plugging Completed 2-20-86

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Rains & Williamson Oil Co. Inc.

ADDRESS 435 Page Court - 220 West Douglas

PHONE (316) 265-9686 OPERATORS LICENSE NO. 5146

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? Yes If not, is well log attached? No

Producing Formation Arbuckle Depth to Top 3816 Bottom 3825 T.D. 3825

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	3816 - 3825			5 1/2	3818	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

5 Titan. Down 5 1/2 - 50 sk. cement + 60/40 poz mix 6% gel 3% C.C. with 2 sk hulls, then 2 sk. hulls with steel, followed by 15 sk gel, then 5 sk hulls, then 30 sk. cement, then 5 sk gel, then 5 sk hulls, sealed plug, followed with 100 sk cement. Max. press. 1700 lbs. Shut in at 500 lbs. Down 8 1/2 sk. Cement 60/40 poz mix 6% gel 3% C.C. Max. press. 150 lbs. Shut in at 100 lbs.
 (If additional description is necessary, use BACK of this form.)
 Plugged down at 2:45 P.M. State agent Margaret Johnson

Name of Plugging Contractor Paul Stephens License No. 683

Address P.O. Box 166

STATE OF Kansas COUNTY OF Pratt, ss.

Rains & Williamson Oil Co. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Paul Stephens

(Address) PO 166 Pratt Ks 67124

SUBSCRIBED AND SWORN TO before me this 26th day of Feb, 19 86

Mary Alice Rupp
 Notary Public

My Commission Expires: 2-29-88

RECEIVED
 STATE CORPORATION COMMISSION

Mary Alice Rupp
 NOTARY PUBLIC
 State of Kansas
 MY COM. EXPIRES 2-29-88

FEB 26 1986
 2-26-86
 CONSERVATION DIVISION

Form CP-4
 Revised 08-84