

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

15-051-00458-00-00

Ellis County, Sec. 6 Twp. 13 Rge. 20W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW SW

Lease Owner Carl Todd Drilling Company

Lease Name Egger Well No. 2

Office Address 404 KFH Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1-14 1954

Application for plugging filed 1-14 1954

Application for plugging approved 1-14 1954

Plugging commenced 1-14 1954

Plugging completed 1-14 1954

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 3874 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	LOG ATTACHED					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 190', set plug and cemented with 15 sacks through drill pipe. Filled hole with mud to 40', set plug and cemented with 10 sacks.

1-26-54
CONSERVATION DIVISION
WICHITA, KAN.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor The Carl Todd Drilling Company
Address 404 KFH Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Carl Todd (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carl Todd
404 KFH Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 25th day of January, 19 54

My commission expires December 14, 1957

Marche Krzyz Notary Public.

PLUGGING
FILE EC 6 T 13 R 20W
BOOK PAGE 9 LINE 6

THE CARL TODD DRILLING COMPANY

404 KFH Building
Wichita, Kansas

#2 Egger
NW NW SW Sec. 6-13-20W
Ellis County, Kansas

COMMENCED: January 4, 1954
COMPLETED: January 14, 1954

15 05100458'00'00

ELEVATION: 2169 KB

CASING RECORD

8-5/8" 18.6# casing set at
200', cemented w/125 sacks

0 - 195	Post rock, sand and shale
195 - 200	Shale
200 - 500	Shale and shells
500 - 730	Shale and shells
730 - 860	Sand and iron
860 - 995	Shale and Red Bed
995 - 1230	Sand
1230 - 1310	Shale, shells and Red Bed
1310 - 1515	Red Bed
1515 - 1550	Anhydrite
1550 - 1645	Shale and shells
1645 - 2115	Red Bed and shale
2115 - 2275	Shale and lime
2275 - 2476	Shale and lime
2476 - 2582	Lime and shale
2582 - 2775	Shale and lime
2775 - 2900	Shale and lime
2900 - 3050	Lime and shale
3050 - 3235	Shale and lime
3235 - 3345	Shale and lime
3345 - 3397	Lime
3397 - 3460	Lime
3460 - 3495	Lime
3495 - 3558	Lime
3558 - 3605	Lime
3605 - 3650	Lime
3650 - 3693	Lime
3693 - 3745	Lime
3745 - 3795	Lime and chert
3795 - 3824	Congl.
3824 - 3828	Lime, shale and chert
3828 - 3835	Arbuckle
3835 - 3853	Arbuckle
3853 - 3874	Lime
3874	Rotary Total Depth

TOPS

Topeka	3208
Heebner	3419
Toronto	3440
Lansing	3456
Base K.C.	3701
Congl.	3799
Arbuckle	3827

DST #1

3829 - 35, open 40 minutes
recovered 10' mud, BHP 70#

DST #2

3833 - 53, open 1 hour,
recovered 20' thin rotary mud
with splotches heavy, sticky
oil, BHP 720#

I hereby certify that the above is a true and correct log to the best
of my knowledge and belief.

THE CARL TODD DRILLING COMPANY

BY Carl Todd

PLUGGING
FILE SEC to T-13 R-20W
BOOK PAGE 9 LINE 6