

Give Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas


WELL PLUGGING RECORD

15-051-05448-00-00

Ellis County, Sec. 6 Twp. 13 Rge. 20 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW  
Lease Owner Henderson Oil Company  
Lease Name Eggers Well No. 1  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 2-28-62 19  
Plugging completed 3-2-62 19  
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well 3834 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	200'	None
				5-1/2"	3830'	211'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3834', ran 20 gal. of sand to 3814' and dumped 4 sacks of cement @ 3814' with dump bailer. Pulled 5 1/2" casing. Pumped in 41 sacks of mud and 58 sacks of cement, let set for 3 hours, removed plug container, checked cement @ 50' and ran 17 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

MAR 20 1962  
3-20-62  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Knight Casing Pulling Company  
Address Chase, Kansas

STATE OF Kansas COUNTY OF Rice  
Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of March, 1962

My commission expires May 20, 1964

Milton J. Tolis  
Notary Public.



THE CARL TODD DRILLING COMPANY  
404 KFH Building  
Wichita, Kansas

15-051-05448-00-00

**RECEIVED**  
STATE CORPORATION COMMISSION

FEB 1 1962

CONSERVATION DIVISION  
Wichita, Kansas

#1 Egger  
SW SW SW Sec. 6-13S-20W  
Ellis County, Kansas

COMMENCED: July 25, 1953  
COMPLETED: August 6, 1953

ELEVATION: 2151 DF

0 - 34	Surface sand & gravel
34 - 200	Shale and shells
200 - 475	Shale and shells
475 - 600	Sand and shale
600 - 850	Shale, iron & sand
800 - 1012	Shale, red bed and sand stks
1012 - 1225	Sand
1225 - 1300	Shale
1300 - 1500	Red bed and shells
1500 - 1535	Anhydrite
1535 - 1585	Shale and shells
1585 - 1890	Shale, iron and shells
1890 - 2010	Shale
2010 - 2165	Shale and lime
2165 - 2255	Lime and shale
2255 - 2425	Lime and shale
2425 - 2500	Lime and shale
2500 - 2655	Shale and lime
2655 - 2815	Shale and lime
2815 - 2905	Lime and shale
2905 - 3060	Shale and lime
3060 - 3170	Shale
3170 - 3246	Lime and shale
3246 - 3270	Lime and shale
3270 - 3360	Lime and shale
3360 - 3415	Lime
3415 - 3453	Lime
3453 - 3490	Lime
3490 - 3540	Lime
3540 - 3590	Lime
3590 - 3622	Lime
3622 - 3675	Lime
3675 - 3735	Lime and shale
3735 - 3770	Lime
3770 - 3805	Lime
3805 - 3820	Shale and lime
3820 - 3834	Lime, sand and shale
3834	Rotary Total Depth

CASING RECORD

Set 8-5/8" at 200' w/ 125 sacks.  
5-1/2" 11# set at 3830' w/100 sacks.

TOPS

Howard	3176
Topelca	3218
Heebner	3430
Toronto	3450
Lansing	3467
B/Kansas City	3708
Marmaton	3715
Arbuckle	3829

DST 3830 - 34, open 1-1/2 hours,  
recovered 150' heavy oil and gas  
cut mud. BHP 930#

I hereby certify that the above is a true and  
correct log to the best of my knowledge and  
belief.

THE CARL TODD DRILLING COMPANY

By:

*Carl Todd*