

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-051-03411-0001
API NUMBER 1-26-38

LEASE NAME J.L. Rumsey

WELL NUMBER 2

SPOT LOCATION S/2 SW/4

SEC. 23 TWP. 11S RGE. 17E (W)

COUNTY Ellis

Date Well Completed 1-26-38

Plugging Commenced 4-26-86

Plugging Completed 4-29-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kerr-McGee Corporation

ADDRESS U.S. Onshore Region, P.O. Box 25861

Oklahoma City, OK 73125

PHONE # (405) 848-9750 OPERATORS LICENSE NO. 6460

Character of Well SWD
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #6, Hays, KS

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation Arbuckle Depth to top 3408 bottom 3412 T.D. 3412

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				10-3/4"	0-1144'	-0-
				7"	0-3405'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. 4-26-86: MI & RU Halliburton. Mixed cement, 10-3/4" to 7" annulus leaking at surface. Dumped 100 lbs cotton seed hulls. Annulus still leaking. RD Halliburton. Split spider bowl, 7" csg. fell below surface. Weld on 1/2" plate steel w/ 2" steel collar looking up. RU Halliburton. Pumped 400 lbs hulls w/ water. Started mixing cement, pumped 300 lbs hulls in cement. Pumped remainder of cement. RD Halliburton. Pump rate 1.5 BPM at 500 psi. Pumped a total of 800 lbs of hulls and 285 sxs Econolite cement.
(If additional description is necessary, use BACK of this form.)

4-29-86: Tag cement at top of surface csg.
Name of Plugging Contractor Halliburton Services License No. 5287
Address Box 428, Hays, KS 67601

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Gaylan Bunas (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is true and correct, so help me God.

STATE CORPORATION COMMISSION

MAY 15 1986

CONSERVATION DIVISION

SUBSCRIBED AND SWORN TO before me this 13 day of May, 19 86

(Signature) Gaylan Bunas

(Address) P.O. Box 25861, Oklahoma City, OK 73125

Nonna M. Bush
Notary Public



My Commission expires: Sept. 13, 1988