

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-051-19367-0001

API NUMBER 3-10-38

LEASE NAME J.L. Rumsey

WELL NUMBER 4

SPOT LOCATION S/2 SW/4

SEC. 23 TWP. 11S RGE. 17 (W)

COUNTY Ellis

Date Well Completed 3-10-38

Plugging Commenced 4-26-86

Plugging Completed 4-29-86

LEASE OPERATOR Kerr-McGee Corporation

ADDRESS U.S. Onshore Region, P.O. Box 25861
Oklahoma City, OK 73125

PHONE # (405) 848-9750 OPERATORS LICENSE NO. 6460

Character of Well SWD
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #6, Hays, KS

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation Granite Wash Depth to top 3884 bottom 3922 T.D. 3922

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				10-3/4"	0-1340'	-0-
				7"	0-3375'	-0-
				4-1/2"	0-3884'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set 4-26-86: MI & RU Halliburton. Pumped 300 lbs cotton seed hulls, had leak in 7" csg. Welder repaired leak. Started pumping & had another leak, repaired and resumed pumping. Pumped 100 lbs of hulls w/ cement. Pumped remainder of cement. Pumped at 3 BPM & 400 psi. Pumped a total of 400 lbs of hulls and 125 sacks Econolite cement. RD Halliburton. 4-29-86: Tag top of cement at 5' below surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287

Address Box 428, Hays, KS 67601

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Gaylan Bunas (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, has filed that the same are true and correct, so help me God.

STATE CORPORATION COMMISSION

(Signature) Gaylan Bunas

(Address) P.O. Box 25861 Oklahoma City, OK 73125

MAY 15 1986
5-15-86
CONSERVATION DIVISION

SUBSCRIBED AND SWORN TO before me this 13 day of May, 1986

Alonna M. Brown
Notary Public

