


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Ellis County, Sec. 23 Twp. 11S Rge. (E) 17 (W)
Location as "NE/CNW&SW" or footage from lines SW SE SE
Lease Owner Cities Service Oil Company
Lease Name Rumsey "A" Well No. 14
Office Address Box 553 Russell, Kansas 67665
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 4-12 19 40
Application for plugging filed 11-12 19 71
Application for plugging approved 11-15 19 71
Plugging commenced 12-16 19 71
Plugging completed 12-29 19 71
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production July 19 69
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Leo Massey
Producing formation Arbuckle Depth to top 3503' Bottom 7' Pen. Total Depth of Well 3510 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1067'	None
				5 1/2"	3504'	1118'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked bottom. Cemented bottom to 3487' with cement. Pulled 5 1/2" casing - parted at 60,000 lbs. - pulled 36 joints (1118.20'). Halliburton pumped in 12 sx. gel, 100 lbs. hulls and 105 sx. cement. Mud 1070' to 530' and cement 530' to surface.

RECEIVED
STATE CORPORATION COMMISSION
APR 13 1972
CONSERVATION DIVISION
Wichita, Kansas
04-13-72

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Co., Inc.
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
E. W. Peterman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) *E. W. Peterman*

Box 553 Russell, Kansas 67665
(Address)

Subscribed before me this 11th day of April, 1972

James F. Kyger

Notary Public.



WELL RECORD

Company Cities Service Oil Co. Well No. 14 Farm Runsey
 Location 330' north & 990' west of SE Cor. Sec. 23 T. 11 R. 17-W
 Elevation 2040 County Ellis State Kansas
 Drig. Comm. March 22, 1940 Contractor Mabee Oil & Gas Company
 Drig. Comp. April 12, 1940 Acid 500 gallons April 13, 1940
 T. D. 3510' Initial Prod. Depthograph: 61,821 oil, no water, 24 hours.

CASING RECORD:

8-5/8" 1067' cem. 300 sx Monarch
 25 sx High Early
 10 sx Aquagel
 5-1/2" 3504' cem. 100 sx Atlas
 10 sx Aquagel

FORMATION RECORD:

rock	0-20
shale & shells	450
sand	530
shale & shells	810
sand	975
shale & shells	1067
red bed & shells	1230
lime	1265
red bed & shells	1440
red bed & shale	1490
shale & shells	1585
shale & salt	1720
shale & shells	1990
lime	2010
shale & shells	2065
shale & lime shells	2139
lime broken	2305
shale	2360
lime broken	2380
lime & shale	2975
lime	3051
lime & shale	3160
broken lime	3491
lime	3497
shale	3504
lime	3505

Top Arbuckle 3504

Rotary T.D. 3505-3504 SIM

dolomite 3510 T. D.

Corr. Top Arbuckle	3503 (-1463)
Penetration	7'
Total Depth	3510

FILLUP: 700' oil in 20 mins.
 1400' oil in 40 mins.
 2500' oil in 1 hrs. 20 mins.
 3000' oil in 1 hr. 40 mins.

SYFO: 1500' 0°
 2000' 0°
 2500' 0°
 3000' 0°

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 15 1971
 CONSERVATION DIVISION
 Wichita, Kansas