

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-051-03408-0080
API NUMBER 9138

LEASE NAME J.L. Rumsey

WELL NUMBER 6

SPOT LOCATION S/2 SW/4

SEC. 23 TWP. 11S RGE. 17 (W)

COUNTY Ellis

Date Well Completed 9-1-38

Plugging Commenced 4-28-86

Plugging Completed 4-29-86

LEASE OPERATOR Kerr-McGee Corporation

ADDRESS U.S. Onshore Region, P.O. Box 25861
Oklahoma City, OK 73125

PHONE # (405) 848-9750 OPERATORS LICENSE NO. 6460

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #6, Hays, KS

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation Arbuckle Depth to top 3468 bottom 3473 T.D. 3473

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	10-Size 3/8"	Put in 0-1215'	Pulled out -0-
				7"	0-3468'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. 4-28-86: MI & RU Halliburton. Pump 500 lbs cotton seed hulls w/ fresh water down 7" csg. Pumped 200 lbs hulls w/ 150 sxs Econolite cement at 2 BPM & 500 psi. Hooked up to 10-3/8" to 7" annulus. Pumped 150 sxs Econolite cement down annulus at 2 BPM & 200 psi. Pumped a total of 700 lbs of hulls & 300 sxs of cement. RD Halliburton. 4-29-86: Tab top of cement at surface of 7" csg.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287
Address Box 428, Hays, KS 67601

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Gaylan Bunas (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

STATE CORPORATION COMMISSION

(Signature) Gaylan Bunas

(Address) P.O. Box 25861
Oklahoma City, OK 73125

MAY 15 1986

CONSERVATION DIVISION
SUBSCRIBED AND SWORN TO before me this 13 day of May, 19 86

Donna M. Rosen
Notary Public



My Commission expires: Sept. 12, 1988