

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Ellis County. Sec. 23 Twp. 11 Rge. 17 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C NE SW SE

Lease Owner Cities Service Petroleum Company

Lease Name Rumsey Well No. 8

Office Address Box 553, Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 5-23-1939

Application for plugging filed 2-9-1961

Application for plugging approved 2-13-1961


Plugging commenced 2-11-1961

Plugging completed 2-15-1961

Reason for abandonment of well or producing formation Non Commercial

If a producing well is abandoned, date of last production November, 1960

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Lvall Shirk

Producing formation Arbuckle Depth to top 3439 Bottom \_\_\_\_\_ Total Depth of Well 3443 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 $\frac{1}{2}$ "-14#	3445'	83 jts.
				8-5/8"-28#	1007'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole w/heavy mud 3443-3400  
Ran 4 sx. cement fillup 3400-3368'  
Pulled pipe to 550'  
Mixed 18 sx. of aquajel and filled hole w/heavy mud  
spotted 20 sx. of cement at 550'  
pulled csg. to 180' - spotted 20 sx. of cement at 180' & filled w/  
heavy mud to 32' - Finished pulling casing - filled hole from 32' to bottom  
of cellar with 10 sx. cement -  
finished plugging @ 3:00 P.M. 2/15/61

RECEIVED  
STATE CORPORATION COMMISSION

FEB 24 1961  
02-24-61  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shull Casing Pulling Company

Address Great Bend, Kansas.

STATE OF KANSAS, COUNTY OF BARTON, ss.

M. M. HARDIN (employee of owner) or ~~conservation commission~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. M. Hardin

Box 553, Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 73rd day of February, 1961

My commission expires March 14, 1963

W. B. Smith  
Notary Public.

15-051-03391-0000

DRILLER'S LOG

Well Owner:	Cities Service Petroleum Company	990' N 990' E S/4
Farm Name:	Rumsey - Well No. 8	Sec. 23-11-17W
Commenced:	5-5-39	
Completed:	5-23-39	Ellis County, Kansas
Total Depth:	3443'	
Casing:	5 1/2" cemented at 3445'	Elevation: Approx. 2000'
	8-5/8" cemented at 1007'	
Contractor:	Shull Casing Pulling Company	Production:

FIGURES BELOW INDICATE BOTTOMS OF FORMATIONS:

Slate	0-25
Shale and Shells	505
Sand	535
Iron Shells and Shale	647
Shale and Shells	997
Shale	1084
Shale	1184
Anhydrite	1191
Shale	1270
Shale and Shells	1503
Salt	1520
Shale	1610
Shale and Lime Shells	1719
Shale and Shells	1800
Broken Lime	1922
Lime	2007
Broken Lime	2110
Lime	2135
Broken Lime	2205
Broken Lime	2230
Shale and Shells	2318
Lime	2340
Broken Lime	2377
Lime and Shale	2475
Broken Lime	2698
Shale	2725
Broken Lime	2828
Shale and Shells	2925
Broken Lime	2933
Lime	3042
Lime	3106
Broken Lime	3180
Lime	3262
Lime	3365
Lime	3405
Broken Lime	3425
Shale and Lime	3440
Dolemite	3438-3440
Lime	3443

RECEIVED  
 CONSERVATION DIVISION  
 WICHITA, KANSAS