


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 23 Twp. 11 Rge. 17 (E) (W)

Location as "NE/CNW%SW%" or footage from lines 330' E 330' S of Center
Lease Owner Cities Service Oil Co.
Lease Name Rumsey Well No. 9
Office Address Box 553 Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 6-7- 1939
Application for plugging filed 7-12- 1960
Application for plugging approved 7-13-6 1960
Plugging commenced 8-8 1960
Plugging completed 8-11 1960
Reason for abandonment of well or producing formation Non-commercial

If a producing well is abandoned, date of last production July 19 60
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. Lewis Brock
Producing formation Arbuckel Depth to top 3386' Bottom 3398' Total Depth of Well 3398 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1030'	-0-
				5 1/2"	3430'	2725'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Run 5 sks cement at 3398'
Pumped 17 sks mud in hole
Pumped 20 sks cement in hole 510'
Pumped 20 sks cement in hole 160'
Mudded to 40'
Set rock bridge to 35'
Run 10 sks cement to cap

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1960
08-23-60
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Shull casing Pulling
Address Great Bend, Kansas


STATE OF Kansas, COUNTY OF Barton, ss.
M.M. Hardin (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M.M. Hardin

Box 553 Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of August 1960

My commission expires March 17, 1963



DRILLER'S LOG

Well Owner: Cities Service Oil Company 330'S 330E of Center
 Farm Name: Rumsey Well No. 9 Sec. 23-11-17W
 Commenced:
 Completed: Ellis County, Kansas
 Total Depth: 3398' Elevation: 1920
 Casing:

Contractor: Shull Casing Pulling Co. Production:

FIGURES BELOW INDICATE BOTTOMS OF FORMATIONS

Shale	-0-	60
Shale and Shells		550
Sand		625
Shale and Lime		814
Shale		1020
Shale		1115
Shale and Red Beds		1175
Anhydrite		1205
Shale and Red Beds		1240
Shale		1460
Salt and Shale		1575
Shale and Shells		1863
Shale and Shells		1937
Broken Lime		2121
Broken Lime		2225
Shale and Shells		2298
Lime		2420
Shale and Shells		2505
Broken Lime		2571
Shale		2693
Shale		2816
Shale and Shells		2835
Broken Lime		2874
Lime and Shale		2900
Lime		2937
Lime		3048
Lime		3092
Broken Lime		3139
Lime		3191
Lime		3268
Lime		3381
Shale and Sand		3390
Dolemite		3387-91
Lime		3391-98
Total Depth		3398

RECEIVED
 OIL CORPORATION COMMISSION
 AUG 23 1950
 08-23-60
 CONSERVATION DIVISION
 Wichita, Kansas