


RECEIVED
 STATE CORPORATION COMMISSION
 JUL 10 1973
 CONSERVATION DIVISION
 Wichita, Kansas
 15-051-05850-0001
 Form CP-4

STATE OF KANSAS
 STATE CORPORATION COMMISSION

Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 P. O. Box 17027
 Wichita, Kansas 67217
 NORTH

WELL PLUGGING RECORD



Locate well correctly on above
 Section Plat

Ellis County, Sec. 22 Twp. 11 Rge. 17 (E) (W)
 Location as "NE/CNWSW" or footage from lines SW SE NW
 Lease Owner Ormand Industries
 Lease Name Bemis B#4 B Well No.
 Office Address Plainville, Kansas 67663
 Character of Well (completed as Oil, Gas or Dry Hole)
 Date well completed 19
 Application for plugging filed 19
 Application for plugging approved 19
 Plugging commenced 6/4/73 19
 Plugging completed 6/7/73 19
 Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
 Producing formation Depth to top Bottom Total Depth of Well 3457 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				15 1/2	36	none
				10-3/4	1131	none
				7"	3414	1509'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3457', ran sand to 3400' and dumped 5 sacks cement.
 Loaded hole, shot pipe at 1686', 1618', 1515', pulled 52 joints,
 Bailed fluid to 400', set rock bridge and dumped 6 yards ready mix.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor KILSO CASING PULLING
 Address CHASE, KANSAS


STATE OF KANSAS COUNTY OF RICE ss.
 R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *R. Darrell Kelso*
 CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 9th day of July 19 73

My commission expires



Margaret Melcher
 Notary Public.

BEMIS B - 4

SW SE NW 22-11-17W
Ellis County, Kansas

15-051-05850-0001

Surface	0 - 36
Shale	36 - 55
Dolomite	55 - 72
Shale & shells	72 - 456
Shale & shells	456 - 667
Shale, shells & sand	667 - 760
Shale & shells	760 - 926
Shale	926 - 1016
Shale & lime	1016 - 1131
Lime & shale	1131 - 1335
Shale & shells	1335 - 1440
Salt	1440 - 1593
Lime, salt & shale	1593 - 1814
Shale & lime	1814 - 1917
Lime & shale	1917 - 2067
Shale & shells	2067 - 2158
Lime	2158 - 2203
Shale & lime	2203 - 2425
Shale	2425 - 2489
Shale & shells	2489 - 2596
Shale, shells & lime	2596 - 2660
Shale & shells	2660 - 2698
Shale & lime	2698 - 2787
Shale & shells	2798 - 2815
Lime	2815 - 2837
Shale & lime	2837 - 2885
Shale	2885 - 2895
Lime	2895 - 3138
Lime & shale	3138 - 3204
Broken lime	3204 - 3242
Lime & shale	3242 - 3257
Broken lime & shale	3257 - 3332
Shale & lime	3332 - 3402
Lime	3402 - 3408
Sand	3408 - 3414
Siliceous lime	3414 - 3457

RECEIVED
STATE CORPORATION COMMISSION
FEB 18 1969
CONSERVATION DIVISION
Wichita, Kansas