


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Ellis County, Sec 22 Twp 11 Rge 17 (E) (W)  
Location as "NE/CNW/SW" or footage from lines SE SE NW  
Lease Owner Ormand Industries  
Lease Name Bemis B#5 B Well No.  
Office Address Plainville, Kansas 67663  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 6/26/73 19  
Plugging completed 6/30/73 19  
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey  
Producing formation Depth to top Bottom Total Depth of Well 3444 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				16"	32'	none
				10-3/4"	1152'	none
				7"	3437'	1806'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Ran sand to 3420' and ran 5 sacks cement. Shot pipe at 2577', 2395', 2088', 1998', 1900', 1811', pulled 59 joints. Loaded hole to 425' and set rock bridge to 410', dumped 7 1/2 yards ready mix.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KESLO CASING PULLING  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
CHASE KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 9th day of July, 1973

My commission expires  
MARGARET MELCHER  
NOTARY PUBLIC  
Rice County, Kansas  
My Commission Expires  
Feb. 15, 1975

Margaret Melcher  
Notary Public.

BEMIS B-5

SE SE NW 22-11-17W  
Ellis County, Kansas

15-051-05851-0000

Shale	0 - 95
Shale, shells & sand	95 - 320
Sand	320 - 412
Sand, iron, shale	412 - 600
Lime	600 - 610
Shale & shells	610 - 700
Sand	700 - 785
Shale	785 - 893
Shale & shells	893 - 1013
Shells & shale	1013 - 1036
Shale	1036 - 1134
Lime	1134 - 1152
Shale & shells	1152 - 1536
Sand & shale	1536 - 1741
Salt	1741 - 1780
Lime	1780 - 2190
Broken lime	2190 - 2240
Lime	2240 - 2282
Lime & shale	2282 - 2365
Lime	2365 - 2400
Lime broken	2400 - 2445
Lime	2445 - 2490
Broken lime & shale	2490 - 2562
Lime & shale	2562 - 2600
Shale	2600 - 2670
Shale & lime	2670 - 2714
Lime & Shale	2714 - 2785
Shale & lime	2785 - 2845
Shale	2845 - 2895
Shale & shells	2895 - 2915
Lime	2915 - 3419
Shale	3419 - 3424
Shale & lime	3424 - 3431
Sand, shale & lime	3431 - 3439
Sand	3439 - 3440
Siliceous lime	3440 - 3441
Lime soft	3441 - 3444

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 18 1969  
CONSERVATION DIVISION  
Wichita, Kansas