


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ellis County, Sec 22 Twp 11 Rge 17 (E) (W)
Location as "NE/CNWSW" or footage from lines NE/4 SE/4 NW/4
Lease Owner Ormand Industries
Lease Name Bemis B Well No. 6
Office Address 2118 Adolphus Tower, Dallas, Texas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed October 18 19 37
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 4/23/69 19
Plugging completed 4/25/69 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production no record 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation Arbuckle Depth to top 3470 Bottom 3474 Total Depth of Well 3474 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	oil	3470	3474	16"	33'	none
				10' 3/4"	1048'	none
				7"	3435'	2369'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked bottom, ran sand to 3425', dumped 7 sacks of cement. Shot pipe at 2375', worked pipe loose, pulled 77 joints. Pumped 5 sacks hulls and 35 sacks gel and 155 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
MAY 20 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss. NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn, on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS (Address)

Subscribed and sworn to before me this 28 day of April 19 69

My commission expires 15/71

Margaret M. Melcher
Notary Public.

BEMIS B - 6

NE SE NW 22-11-17W
Ellis County, Kansas

15-051-05852-0000

Shale	0 - 33
Shale & shells	33 - 315
Broken Lime & shale	315 - 580
Sand	580 - 595
Shale	595 - 743
Red rock, sand, shells	743 - 1002
Red beds & shale	1002 - 1105
Shale	1105 - 1363
Shale & shells	1363 - 1451
Salt & shale	1451 - 1580
Salt & shale	1580 - 1670
Shale & shells	1670 - 1685
Lime	1685 - 1755
Lime & shale	1755 - 1805
Broken lime & slate	1805 - 1835
Shale & shells	1835 - 1900
Shale & lime	1900 - 1979
Broken lime & shale	1979 - 2053
Shale & lime	2053 - 2090
Shale	2090 - 2130
Lime	2130 - 2148
Lime & shale	2148 - 2280
Broken shale & lime	2280 - 2375
Broken lime	2375 - 2480
Broken lime & shale	2480 - 2530
Lime	2530 - 2557
Broken lime & shale	2557 - 2661
Lime	2661 - 2682
Lime & shale	2682 - 2742
Broken lime & shale	2742 - 2790
Lime	2790 - 3125
Shale	3125 - 3140
Lime	3140 - 3398
Broken shale & lime	3398 - 3420
Shale	3420 - 3428
Simpson sand	3428 - 3436
Siliceous lime	3436 - 3447
Lime	3447 - 3474

RECEIVED
STATE CORPORATE COMMISSION
FEB 18 1950
CONSERVATION DIVISION
Wichita, Kansas