

RECEIVED
STATE CORPORATION COMMISSION


15-051-05853-0001 JUL 10 1973

CONSERVATION DIVISION CP-4
Wichita, Kansas

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ellis County, Sec. 22 Twp. 11 Rge. 17 (E) (W)
Location as "NE/CNWSW" or footage from lines Bemis B#7 B C N/2 S/2 NW
Lease Owner Ormand Industries
Lease Name Bemis B#7 B Well No.
Office Address Plainville, Kansas 67663
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 6/8/73 19
Plugging completed 6/8/73 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation Depth to top Bottom Total Depth of Well 3436 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9-5/7	1200	none
				5 1/2"	3415'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set bridge at 1400' and dumped 5 sacks cement. Mud to 420',
rock bridge to 410' and filled to base of cellar with ready mix.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KELSO CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss.
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 9th day of July 19 73

My commission expires
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975



Margaret Melcher
Notary Public.

BEMIS B - 7

C N/2 S/2 NW 22-11-17W
Ellis County, Kansas

15-051-05853-0007

Shale	0 - 103	Shale & Broken Lime	2753 - 2840
Shale & lime shells	103 - 325	Lime & strks shale	2840 - 2874
Sand & streaks of shale	325 - 579	Lime	2874 - 2937
Hard lime & iron	579 - 601	Shale	2937 - 2960
Shale & iron	601 - 672	Lime	2960 - 3025
Sandy shale	672 - 710	Lime & strks shale	3025 - 3061
Shale & iron	710 - 715	Lime	3061 - 3105
Shale & bentonite	715 - 774	Cherty lime	3105 - 3117
Sandy shale & iron	774 - 782	Broken lime & shale	3117 - 3192
Red bed & shale	782 - 970	Lime	3192 - 3206
Shale & strks sand	970 - 1002	Lime & anhydrite	3206 - 3249
Shale & pyrite	1002 - 1128	Lime	3249 - 3370
Anhydrite & iron	1128 - 1175	Shale	3370 - 3378
Red bed & shale	1175 - 1380	Conglomerate &	
Shale & shells	1380 - 1496	strks of chert	3378 - 3394
Salt, shale & shells	1496 - 1676	Shale	3394 - 3407
Salt	1676 - 1680	Sand	3407 - 3410
Anhydrite & shale	1680 - 1788	Shale	3410 - 3411
Broken lime & shale	1788 - 1815	Lime	3411 - 3446
Shale	1815 - 1838		
Lime	1838 - 1857		
Broken lime	1857 - 1914		
Lime w/ streaks anhydrite			
& shale	1914 - 2021		
Broken lime & shale	2021 - 2045		
Shale	2045 - 2088		
Lime	2088 - 2100		
Shale	2100 - 2120		
Lime	2120 - 2130		
Shale	2130 - 2165		
Shale & iron pyrite	2165 - 2188		
Lime & strks shale	2188 - 2240		
Shale	2240 - 2265		
Broken lime & shale	2265 - 2287		
Sandy shale	2287 - 2305		
Lime	2305 - 2320		
Shale	2320 - 2342		
Lime	2342 - 2390		
Shale & lime	2390 - 2428		
Broken lime & shale	2428 - 2443		
Lime, pyrite & shale	2443 - 2461		
Shale & shells	2461 - 2528		
Lime	2528 - 2539		
Shale & broken lime	2539 - 2695		
Lime	2695 - 2753		

RECEIVED
STATE CORPORATION COMMISSION
FEB 18 1969
CONSERVATION DIVISION
Wichita, Kansas