


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plot

Ellis County. Sec. 22 Twp. 11 Rgs. 17 (E) (W)  
Location as "NE/CNW/SE/SW" or footage from lines C N/2 SW NW  
Lease Owner Ormand Industries  
Lease Name Bemis B# Well No. 8-B  
Office Address Plainville, Kansas 67663  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 4/16/73 19  
Plugging completed 4/18/73 19  
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey  
Producing formation Depth to top Bottom Total Depth of Well 3490 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	1095	none
				5 1/8"	3489	1557'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 1764', found bridge and couldn't knock it out. Set rock bridge and dumped 5 sacks cement. Loaded hole, shot pipe at 1690', 1560', pulled 49 joints. Set rock bridge and sand bridge from 435' to 375', bailed fluid down and dumped 6 yards ready mix.

RECEIVED  
STATE CORPORATION COMMISSION

APR 20 1973

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING COMPLETE.

Name of Plugging Contractor (If additional description is necessary, use BACK of this sheet)  
KELSO CASING PULLING  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss.  
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
CHASE, KANSAS

(Address)

Subscribed and sworn to before me this 18th day of April, 1973  
MARGARET MELCHER  
NOTARY PUBLIC  
Rice County, Kansas  
My Commission Expires Feb. 15, 1975

My commission expires

Margaret Melcher  
Notary Public.

BEMIS B - 8

C N/2 SW NW 22-11-17W  
Ellis County, Kansas

15-051-05039-0000

Shale	0 - 315
Sand	315 - 425
Sand & shale	425 - 580
Lime	580 - 605
Pyrite & sand	605 - 650
Sand	650 - 735
Shale & shells	735 - 1100
Red bed	1100 - 1130
Anhydrite	1130 - 1170
Shale & shells	1170 - 1490
Salt & shale	1490 - 1670
Shale	1670 - 1800
Shale & lime	1800 - 2035
Lime & shale	2035 - 2270
Shale & lime strks	2270 - 2325
Lime & shale	2325 - 2830
Lime	2830 - 2890
Lime & shale	2890 - 2975
Lime	2975 - 3485
Dolomite	3485 - 3496

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 18 1969  
CONSERVATION DIVISION  
Wichita, Kansas