


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Location as "NE/CNW&SW&" or footage from lines Ellis County. Sec. 22 Twp. 11 Rge. (E) 17 (W) NW SE ST
Lease Owner Sohio Petroleum Company
Lease Name Bemis "C" Well No. 3
Office Address Box 673, Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 5-18 19 37
Application for plugging filed 2-7 19 59
Application for plugging approved 2-9 19 59
Plugging commenced 3-9 19 59
Plugging completed 3-10 19 59
Reason for abandonment of well or producing formation Uneconomical



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production March 19 57
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Arbuckle Depth to top _____ Bottom _____ Total Depth of Well 3478 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle				7"	3470'	2614'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped sand to 3460' with 5 sacks cement, loaded hole with water.
Pulled to 550'. Circulated with 35 sacks mud and 30 sacks cement.
Pulled to 180', pumped 30 sacks cement. Pulled pipe. Placed 5'
rock bridge and cemented to top of cellar with 10 sacks cement.

MAR 16 1960 03-16-59

CON. DIVISION
WICHITA

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
J. H. Bond (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. H. Bond
(Address) _____

SUBSCRIBED AND SWORN TO before me this 12th day of March, 19 59

My commission expires March 25, 1961

Marjorie Lee Sumner
Notary Public.

PLUGGING
FILE SEC. 22 T. 11 R. 7W
BOOK PAGE 14 LINE 35

15-051-05831-0000

LOG OF MARGARITON CORPORATION

Section 22-T-11, Hill, County, Kansas

2 1/2" casing
Completed 11/1/59

FROM	TO	FORMATION	FROM	TO	FORMATION
0	25	Collar	2256	2270	Shale
25	55	Shale	2270	2322	Shale & shells
Set & cemented 1 1/2" casing			2322	2394	Shale & shells
with 55 sacks cement			2394	2402	Shale
55	153	Shale	2402	2456	Shale & shells
153	370	Shale & shells	2456	2526	Shale
370	590	Sand & shells	2526	2717	Shale
590	700	Pyrites of iron	2717	2793	Shale & shells
700	784	Shale & shells	2793	2848	Shale
784	886	Sand	2848	2912	Shale & shells
886	887	Shale & shells	2912	2944	Shale
887	1198	Red rock & shale	2944	2958	Lime
1198	1213	Chalk	2958	2967	Shale
Set & cemented 10" casing with			2967	2976	Lime
380 sacks cement			2976	3086	Shale & shells
1213	1242	Anhydrite	3086	3090	Shale
1242	1410	Red bed & shale	3090	3142	Sandy shale & lime
1410	1580	Red beds, shale & salt	3142	3191	Broken lime
1580	1575	Red rock & shale	3191	3207	Sticky shale
1575	1730	Salt	3207	3248	Sandy shale & lime
1730	1790	Salt & shale	3248	3325	Sandy shale & lime
1790	1874	Lime, broken	3325	3352	Lime
1874	1887	S. L. M. Correction	3352	3392	Lime & shale
1887	1980	Broken lime	3392	3453	Broken lime
1980	2092	Shale & lime	3453	3460	Red shale
2092	2126	Sticky shale & lime	3460	3475	Shale
2126	2206	Shale & shells	3475	3476	Shale
2206	2217	Lime	Set & cemented 7" casing		
2217	2232	Shale	with 800 sacks cement		
2232	2266	Lime	3476	3478	Shale & shells

RECEIVED
STATE CORPORATION COMMISSION

FEB 6 1959

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING	
FILE	SEC. 22 T. 11 R. 17W
BOOK	PAGE 14 LINE 35