


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Ellis County. Sec. 22 Twp. 11 Rge. 17 (E) 17 (W)  
Location as "NE/CNW/SW" or footage from lines. SW NE SW  
Lease Owner Sohio Petroleum Company  
Lease Name Bemis "C" Well No. 2  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 5-4 1937  
Application for plugging filed 2-7 1959  
Application for plugging approved 2-9 1959  
Plugging commenced 2-21 1959  
Plugging completed 2-26 1959  
Reason for abandonment of well or producing formation uneconomical

If a producing well is abandoned, date of last production December 1957  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Arbuckle Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3515 1/2 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle				7"	3458'	2423'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with sand to 3300' and dumped 5 sacks of cement on top of sand. Pulled casing to 500', circulated using 25 sacks jel and spotted 30 sacks of cement through casing. Pulled pipe to 180'; pumped in 30 sacks of cement. Placed 5' rock bridge at 30' with 10 sacks of cement on top of bridge to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 5 1959

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.  
J. H. Bond (employee of owner) ~~EX (owner of property)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. H. Bond  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 2nd day of March, 1959

My commission expires March 25, 1961 \_\_\_\_\_ Notary Public.

PLUGGING  
FILE SEC. 22 T. 11 R. 17  
BOOK PAGE 14 LINE 34

Series C-2 Drilling Time & Sample Description

<u>Depth</u>	<u>Drilling Time (Min.)</u>	<u>Sample Description</u>
3489-90 $\frac{1}{2}$	20	Large cuttings - some stain
92	30	" " " " " "
93	15	Fine white Cryst. Dol. & Chert.
94	25	" " " " " "
95	45	" " " " " "
96	45	" " " " " "
97	55	" " " " " "
98	1:20	" " " " " " Few breaks - trace of ls.
99	1:00	Fine white Cryst. Dol. & Chert.
3500	35	Same--some small dark specks.
01	45	Same--lined.
02	35	Notable increase in grey shale peppered with bl. ss.
03	25	No change.
04	45	Samples larger--some Inter. Chert. Por. No show.
05	40	Firm cuttings.
06	45	Some pink dol.
07	35	" " "
08	40	Some decrease in shale.
09	45	" " " "
10	1:00	questionable stain
11	1:00	White Chert. & pink dol.
13	35	Pink dol.--some Inter. & trace grey shale. No show.
3514	25	Cherty dol.--coarse--some fair to good int. except. por.-- scattered with grey shale & pi dol. (wet samples--up to 1% oil live--some samples showed good even staining).

206.41' of 5 $\frac{1}{2}$ " 14# 10V thd; screwed liner set at 3513.00' Cemented with 100 sacks posmix.

<b>PLUGGING</b>
FILE SEC <u>22</u> T. <u>11</u> RITW
BOOK PAGE <u>14</u> LINE <u>34</u>