


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 So. Broadway
Wichita, Kansas

15-051-19376. 0000
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Ellis County, Sec. 22 Twp. 11S Rge. 17 (E) (W)
Location as "NE/CNW/SW" or footage from lines SW/SW/SW
Lease Owner Toland and Reeves
Lease Name F.A. Bemis Well No. #4
Office Address Box 4336, Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed Yes 19
Application for plugging approved Yes 19
Plugging commenced 4-17 19 57
Plugging completed 5-24 19 57
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3476' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"		No pipe got off of well

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Measured into TD 3476'.
Plugging started 4-17-57. Finished 5-24-57.
Plugged off bottom with sand to 3440' and dumped 5 sacks cement with bailer. Shot 7" casing. Squeezed well with 60 sacks Jel Mud and 100 sacks cement. Pulled plug container and capped well with 6 sacks cement. Well completed. (Shot pipe at 3440')

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of May, 1957.

My commission expires November 8, 1960.
Notary Public.

05-28-57
PLUGGING
SEC 22 T11 R17W
BOOK PAGE 147 10

WELL RECORD

15-051-19376-0000

British American Oil Prod. Co.

F. A. Bemis #4

Located: SW/4 of Section 22-118-17W,
Ellis County, Kansas

Sw Sw Sw

	From	To		From	To
Cellar	0	10	Shale & lime	3463	3466
Surface clay	10	25	Siliceous lime	3466	3476
Clay & shells	25	147	Total Depth	3476	
Shale	147	155	Set 15 1/2"		
Shale & shells	155	280			
Shells	280	292			
Pirities of Iron	292	300			
Shale & boulders	300	435	Drilling commenced	2-5-37	
Sand	435	485	Drilling completed	3-7-37	
Shale & shells	485	570			
Sand	570	615	Elevation	1938.5'	
Pirities of iron	615	625			
Shale & shells	625	765	First potential, 2949 bbls.	3-12-37	
Shale	765	840			
Lime & shale	840	950			
Pirities of iron	950	960	<u>CASING RECORD</u>		
Shale	960	985	16" OD Set at 142'	Cemented w/ 130 sacks	
Shale & pirities of iron	985	1000	10 5/4" " " 1200'	" " 525 "	
Shale and shells	1000	1130	7" OD " " 3453'	" " 180 "	
Red bed & shells	1130	1192			
Chalk	1192	1196			
Anhydrite	1196	1219	Set 10"		
Red bed	1219	1350			
Shale	1350	1400			
Shale & red beds	1400	1472			
Shale & shells	1472	1490			
Salt	1490	1740			
Shale	1740	1765			
Lime & shale	1765	1848			
Shale & shells	1848	1900			
Lime	1900	1920			
Broken lime	1920	1960			
Shale	1960	2015			
Lime	2015	2041			
Shale & shells	2041	2058			
Lime & shale	2058	2120			
Shale & shells	2120	2160			
Broken lime	2160	2175			
Shale & shells	2175	2230			
Broken lime	2230	2315			
Shale	2315	2325			
Broken lime	2325	2360			
Shale & lime	2360	2400			
Broken lime & shale	2400	2440			
Shale & shells	2440	2476			
Lime & shale	2476	2542			
Shale & shells	2542	2715			
Shale & lime	2715	2735			
Shale & shells	2735	2830			
Lime	2830	2840			
Shale & shells	2840	2870			
Shale & lime	2870	2915			
Broken lime	2915	2931			
Lime, Topeka	2931	3095			
Shale	3095	3110			
Lime	3110	3189			
Broken lime	3189	3205			
Lime, Kansas City	3205	3445			
Green shale	3445	3450			
Lime	3450	3466			

03-12-37

PLUGGING			
FILE	SEC	22 T. 11	R. 17W
BOOK	PAGE	147	LINE 10