


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Location as "NE/CNW&SW&" or footage from lines Ellis County. Sec. 22 Twp. 11 Rge. (E) 17(W)
Lease Owner Sohio Petroleum Company
Lease Name Bemis "C" Well No. 6
Office Address Box 673, Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 6-3 19 37
Application for plugging filed 2-7 19 59
Application for plugging approved 2-9 19 59
Plugging commenced 3-4 19 59
Plugging completed 3-8 19 59
Reason for abandonment of well or producing formation Uneconomical



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production March 19 57
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Arbuckle Depth to top _____ Bottom _____ Total Depth of Well 3497 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle				7"	3489'	2317'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped sand to 3470' with 5 sacks of cement on top. Pulled 56 joints.
Pumped 25 sacks mud at 550' and 30 sacks of cement. Pulled to 180';
pumped 30 sacks cement. Placed 5' rock bridge and cemented to top of
cellar with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAR 12 1959
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
J. H. Bond (employee of owner) ~~or (owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. H. Bond
(Address) _____

SUBSCRIBED AND SWORN TO before me this 10th day of March, 19 59

My commission expires March 25, 1961 Marjorie (see above) Notary Public.

PLUGGING
FILE NO. 22 T. 11 R. 17W
BOOK PAGE 14 LINE 37

15-051-05834-0000

LOG OF MARY KAY OIL CORPORATION
 No. 22-19-157, E. 1/2 Sec. 14, T. 11N, R. 17W

05-12-37

Completed

04-03-37

FROM	TO	FORMATION	FROM	TO	FORMATION
0	10	Cellar	2072	2177	Shale
10	20	Surface clay & lime	2187	2287	Shale
Set & cemented 15 1/2" casing with 18 sacks cement			2267	2282	Shale
20	455	Shale & shells	2282	2302	Shale
455	585	Red rock	2302	2435	Shale
585	590	Shale & shells	2435	2437	Shale
590	700	Sand & shale	2437	2470	Shale
700	795	Shale	2470	2732	Shale
795	820	Sand	2732	2817	Shale
820	1180	Shale & shells	2817	2837	Shale
1180	1217	Red rock & shale	2837	2872	Shale
1217	1225	Chalk	2872	2927	Shale
1225	1227	Anhydrite	2927	3096	Shale
Set & cemented 10" casing with 300 sacks cement			3096	3135	Shale
1227	1260	Anhydrite	3135	3222	Shale
1260	1510	Shale	3222	3242	Shale
1510	1445	Red rock	3242	3247	Shale
1445	1500	Red rock & shale	3247	3270	Shale
1500	1561	Shale & shells	3270	3275	Shale
1561	1563	Shale	3275	3481	Shale
1563	1780	Salt & shale	3481	3485	Shale
1780	1842	Shale & lime	3485	3485	Shale
1842	1885	Broken lime			
1885	2072	Broken lime & shale			

341 89
 2022
 467

RECEIVED
 STATE CORPORATION COMMISSION

FEB 6 1959

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 22 T. 11 R. 17W
 BOOK PAGE 14 LINE 37