

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-97594-00 ⁰⁵⁸¹¹⁻⁰⁰⁰⁰

LEASE NAME Johansen-Schmeidler

WELL NUMBER A-2

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

330 Ft. from S(N) Line of Section (circle one)

1650 Ft. from (E/W Line of Section (circle one)

LEASE OPERATOR Liberty Operations & Completions, Inc

SPOT LOCATION C - NE - NW - NE

ADDRESS 308 W Mill

SEC. 22 TWP. 11 S. RGE 17 (E) or (W)

CITY, STATE, ZIP Plainville, Ks. 67663

COUNTY Ellis

PHONE#(913) 434-4686 OPERATORS LICENSE NO. 8925

Date Well Completed 8/1937

Charater of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced 12/16/96

Date Plugging Completed 12/16/96

The plugging proposal was approved on 12/11/96 (date)

by Carl Goodrow (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation(s) Arbuckle Depth to Top 3440 Bottom T.D. 3449

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Arbuckle	open hole			16"	103'	0
				10 3/4"	1136'	0
				7"	3443	0
Hole clean to T.D.	No junk in hole					

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dig out cellar

Remove casing hanger weld. 10 3/4" to 7" casing. Fill both 7" & 10 3/4" w/cement pump 75 sx 60/40 poz 10% gel with 5 sx cotton seed hulls. Followed with 20 sx gel. and 225 sx 60/40 poz 10% gel. Pressure max 500# shut in 250#. Pressure annulus to 500# Could not pump in.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co

License No. N.A.

Address Russell, Ks.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Liberty Operations & Completions, Inc.


12-18-96

STATE OF Kansas COUNTY OF Ellis, ss.

Charles D. Farr (Employee of Operator or (Operator) of above-described well, being first
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Charles D. Farr

(Address) Hays, Ks. 67601



SUBSCRIBED AND SWORN TO before me this 17 day of December, 19 96

Sandra Chandi
Notary Public

My Commission Expires: 9/15/98