


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW&SW&" or footage from lines 11 22 11 17 (W)
Lease Owner Sohio Petroleum Company
Lease Name Johansen Well No. 6
Office Address Box 673, Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 7-15 1958
Application for plugging filed 12-22 1958
Application for plugging approved 12-21 1958
Plugging commenced 1-27 1959
Plugging completed 1-31 1959
Reason for abandonment of well or producing formation uneconomical

If a producing well is abandoned, date of last production December 1958
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Arbuckle Depth to top _____ Bottom _____ Total Depth of Well 3387 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle				7"	3380'	1520.34'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3387' to 3370' - Dumped sand and 5 sacks cement on top of sand.
Pulled 34 joints to 450'. Pumped 20 sacks mud into casing and mixed and spotted 30 sacks cement. Pulled 8 additional joints to 180', pumped in 30 sacks cement. Pulled all of pipe.
Placed 5' rock bridge, dumped 10 sacks cement up to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
FEB 4 1959
02-04-59

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
J. H. Bond (employee of owner) or owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. H. Bond
(Address) _____

SUBSCRIBED AND SWORN TO before me this 3rd day of February, 1959
Russell M. Miller
Notary Public.

My commission expires July 2, 1961

22 11 17W
6 6

WORTHINGTON, MISSOURI
SECTION 22-11-17W, Ellis County, Kansas

Commenced: 4-21-39
Completed: 5-15-38

FROM TO FORMATION

0 8 Cellar
8 35 Surface clay
Set & cemented 15 1/2" casing with
12 sacks cement

35 505 Shale & shells
505 570 Sand
570 596 Sandy shale
596 612 Pyrites of iron
612 648 Red bed
648 699 Shale & shells
699 768 Sand
768 849 Shale & shells
849 1049 Red bed
1049 1118 Shale & shells
1118 1118 Chalk
1118 1121 Anhydrite

Leak
Chug

Set & cemented 10" casing with
358 sacks cement at 1121'

1121 1160 Anhydrite
1160 1249 Red bed
1249 1768 Shale & shells
1768 1768 Lime
1768 1848 Broken lime
1848 1999 Shale & shells
1999 2066 Broken lime
2066 2166 Shale, sticky
2166 2255 Broken lime
2255 2255 Red shale
2255 2300 Broken lime
2300 2326 Lime & shale
2326 2326 Broken lime
2326 2345 Shale
2345 2435 Shale & shells
2435 2545 Lime & shale
2545 2619 Shale & shells
2619 2707 Shale & lime
2707 2792 Shale & shells
2792 2928 Broken lime
2928 2928 Lime
2928 3000 Broken lime
3000 3122 Lime
3122 3122 Lime & shale
3122 3226 Lime
3226 3245 S. L. M. Correction
3245 3275 Lime
3275 3375 Green shale
3375 3380 Sand
3380 3380 Sand & shale
3380 3385 Lime

Set & cemented 7" O. D. casing
with 150 sacks cement

3385 3507 Lime, oil

RECEIVED
STATE CORPORATION COMMISSION

DEC 23 1958

PLUGGING
FILE SEC 22-T 11-17W
BOOK PAGE 6 LINE 6