


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-051-01668-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Ellis County. Sec. 22 Twp. 11 Rge. (E) 17 (W)  
Location as "NE/CNWxSWx" or footage from lines SE SE SE  
Lease Owner Sohio Petroleum Company  
Lease Name Johansen Well No. 7  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 10-28 19 57  
Application for plugging filed 12-22 19 58  
Application for plugging approved 12-24 19 58  
Plugging commenced 1-14 19 59  
Plugging completed 1-19 19 59  
Reason for abandonment of well or producing formation uneconomical

If a producing well is abandoned, date of last production December 19 58  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Arbuckle Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3381 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Arbuckle</u>				<u>7"</u>	<u>3372'</u>	<u>2623'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

3381' to 3360' = sand and 5 sacks cement. Spotted 30 sacks of cement through 7" casing at 400'. Pulled pipe at 180' and spotted 30 sacks of cement. Placed 5' rock bridge at 30'. Dumped 10 sacks cement to bottom of cellar.

STATE CORPORATION COMMISSION  
JAN 26 1959  
CONSERVATION DIVISION  
01-26-59

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor West Supply Company  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.  
J. H. Bond (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. H. Bond  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN to before me this 20th day of January, 19 59

My commission My Commission Expires July 2, 1961  
Russell M. Miller Notary Public.

PLUGGING  
FILE SEC 22 T 11 R 17W  
BOOK PAGE 6 LINE 7

LOG OF WELLS OF THE CORPORATION  
 Section 22 T. 11 S. R. 17 W.

Commenced 12-23-58  
 Completed 12-23-58

FROM	TO	DESCRIPTION
0	8	Collar
8	22	Surface clay
22	24	Sand & gravel
24	28	Shale
Set & cemented 24' of 1 1/2" casing with 15 sacks cement		
28	325	Shale & shells
325	490	Red bed
490	535	Sand
535	682	Shale & shells
682	758	Sand
758	899	Red bed & shells
899	1107	Red rock & shells
1107	1110	Chalk
1110	1115	Anhydrite
Set & cemented 1115' of 10 3/4" casing with 325 sacks cement		
1115	1155	Anhydrite
1155	1240	Red beds & shells
1240	1499	Shale & shells
1499	1581	Shale & shells, salt
1581	1703	Broken line & anhydrite
1703	1802	Broken line
1802	1887	Line
1887	1968	Broken line
1968	2215	Line
2215	2385	Broken line
2385	2528	Line
2528	2560	Broken line
2560	2786	Shale & shells
2786	2840	Broken line & line
2840	2880	Broken line
2880	2968	Line
2968	2984	Line, cherry
2984	3008	Line, hard
3008	3364	Line
3364	3365	Green shale
3365	3370	Sand
3370	3375	Siliceous line
Set & cemented 7" O. D. casing with 150 sacks cement		
3375	3381	Line

PLUGGING  
 FILE SEC 22 T. 11 S. R. 17 W  
 BOOK PAGE 6 LINE 7

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 23 1958  
 12-23-58  
 CONSERVATION DIVISION  
 Wichita, Kansas