


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 22 Twp. 11 Rge. (E) 17(W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. NE NE NE
Lease Owner. Cities Service Oil Company
Lease Name. Johansen "A" Well No. 7
Office Address. Bartlesville, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole). Oil
Date well completed. 11-20 19.37
Application for plugging filed. 5-24 19.46
Application for plugging approved. 5-24 19.46
Plugging commenced. 5-27 19.46
Plugging completed. 6-1 19.46
Reason for abandonment of well or producing formation. Unprofitable

If a producing well is abandoned, date of last production. May 19.46
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well. Mr. Herb Kerr
Producing formation. Arbuckle lime Depth to top. Bottom. Total Depth of Well. 3404 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle lime	Water			15 1/2	93'	None
				10 3/4	1094	None
				7"	3398	2481'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped 6 sacks of cement @ 3404 filled with mud to 250' -
dumped 20 sacks of cement @ 250' mud to 15' - dumped 10 sacks of
cement, mud and dirt to surface.

22 11 17W
55 2



06-18-46

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Mr. R. C. Hauber
Address. Cities Service Oil Company Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Mr. James Porter (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 553 Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of June 1946

My commission expires. mch 17-1947

Notary Public.

WELL RECORD

Company Cities Service Oil Co. Well No. 7 Farm Johansen "A"
 Location 330' South and 330' West of NE Corner Sec. 22 T. 11 R. 17W
 Elevation _____ County Ellis State Kansas
 Drlg. Comm. October 16, 1937 Contractor John E. Mabey
 Drlg. Comp. November 17, 1937 Acid 2000 gallons - Nov. 28, 1937
 T. D. 3404' Initial Prod. 1664 oil, 0 water, 24 hours (after acid)

CASING RECORD:

15-1/2" 93' cem. 97 sacks
 10-3/4" 1094' cem. 500 sacks
 7" 3397' SLM cem. 250 sacks

FORMATION RECORD:

surface sand, sticky shale
 & shells 93
 shale & shells 422
 shells & sand 544
 iron pyrite 555
 sand & shale 750
 shale, shells & red beds 1045
 red beds 1090
 lime 1095
 anhydrite 1130
 shale 1182
 red beds & shale 1440
 salt 1671
 shale & lime 1812
 shale & shells 1942
 lime & shale 2018
 broken lime 2068
 lime 2190
 lime & shale 2270
 sandy shale 2370
 lime 2421
 lime & shale 2481
 lime 2533
 lime & shale 2699
 shale 2770
 lime 3092
 broken lime 3156
 lime 3387
 shale (cored) 3395
 lime (cored) 3396
 SLM Corr. 3396 = 3397
 lime 3404 T. D.

Top Siliceous 3396' SLM
 Penetration 8'
 Total Depth 3404'

FILLUP: 400' oil in 45 mins.
 1000' oil in 1-3/4 hrs.
 1900' oil in 4-1/4 hrs.
 2500' oil in 6-1/4 hrs.
 Fluid level 2850'

SYFO: 1500' OK
 2000' OK
 2500' OK
 3000' OK

22 11 17W
 55 2