


KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-051-06212-0000

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

County. Sec. 22 Twp. 11 Rge. (E) 17 (W)
Location as "NE/CNW/SW" or footage from lines NW SW SE
Lease Owner Sohio Petroleum Company
Lease Name Johansen Well No. 2
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 7-26 19 37
Application for plugging filed 2-17 19 61
Application for plugging approved 2-20 19 61
Plugging commenced 3-25 19 61
Plugging completed 3-31 19 61
Reason for abandonment of well or producing formation Uneconomical

If a producing well is abandoned, date of last production October 19 59
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Arbuckle Depth to top _____ Bottom _____ Total Depth of Well 3428 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				16"	30'	--
				10-3/4"	1171'	--
				7"	3427'	2482'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3428 to 3418 Dump sand and 5 sacks cement
3418 to 400 Pumped in mud
400 to 160 Spotted 20 sacks cement and 5 sacks jell
160 to Cellar Pumped in 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
APR 5 1961
04-05-61

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Co.
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
J. H. Bond (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. H. Bond
(Address) _____

SUBSCRIBED AND SWORN TO before me this 4th day of April, 19 61

My commission expires June 30, 1962
William J. Bond
Notary Public.



LOG OF MARGAY OIL CORPORATION JOHANSBURG #2
 Section 22-118-17W, Ellis County, Kansas

Commenced: 4-30-37
 Completed: 7-26-37

FOOT TO FORMATION

FOOT	TO	FORMATION
0	39	Clay
Set & cemented 15 1/2" casing		
39	400	Shale & shells
400	485	Red shale & shells
485	605	Sand
605	725	Shale & shells
725	820	Sand
820	887	Shale & shells
887	1001	Sticky red shale
1001	1091	Sticky shale & shells
1091	1125	Red sticky shale
1125	1132	Pyrites of iron
1132	1152	Sticky shale
1152	1166	White chalk
1166	1171	Anhydrite
Set & cemented 1 1/2" 10" O. D. casing with 320 sacks cement		
1171	1225	Anhydrite
1225	1325	Red shale & shells
1325	1371	Shale & shells
1371	1425	Red sticky shale
1425	1711	Shale & shells
1711	1804	Broken lime
1804	2041	Shale & shells
2041	2172	Lime
2172	2414	Broken lime
2414	2454	Broken lime, sticky shale
2454	2520	Sticky shale & shells
2520	2560	Sticky shale
2560	2700	Shale & shells
2700	2745	Lime
2745	2922	Broken lime
2922	2944	Shale & shells, sticky
2944	3420	Lime
3420	3425	S. L. M. Concretion
3425	3427	Lime; Siliceous
Set & cemented 7" O. D. casing with 120 sacks cement		
3427	3428	Lime

RECEIVED
 STATE GEOLOGICAL COMMISSION

MAR 2 1937

CONSERVATION DIVISION
 Wichita, Kansas