


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

T - 11S NORTH R - 17W



Locate well correctly on above Section Plat

ELLIS County. Sec. 22 Twp. 11S Rge. 17W (E) (W)
Location as "NE/CNWxSWx" or footage from lines NE c SE
Lease Owner FRANK J. BLACK
Lease Name S. JOHANSEN Well No. 11
Office Address Box 150, McPherson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 3-31-38 19
Application for plugging filed 10-4-65 19
Application for plugging approved 10-5-65 19
Plugging commenced November 5, 1965 19
Plugging completed November 9, 1965 19
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well GILBERT LEIKER, VICTORIA, KANSAS
Producing formation Depth to top Bottom Total Depth of Well 3396 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				16"	58'	None
				10-3/4"	1130'	None
				7"	3392'	2503'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged, back with sand to 3380- feet, dumped 5- sacks cement.
Circulated Mud at 500- feet, pumped 25- sacks cement at 450- feet.
Pumped 25- sacks cement at 200- feet, put ten sacks on top.

PLUGGING COMPLETE.

NOV 19 1965
11-19-65

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor LYNCH CASING PULLING COMPANY. NO 457
Address R.Rt. 4 GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF MCPHERSON, ss.
Frank J. Black (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) [Signature]
Box 150, McPherson, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of November, 1965

My commission expires July 16, 1967

Jerry Peltzman
JERRY PELTZMAN Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.


15-051-19378-0000

MAGNOLIA PETRO. CO.
J. Johansen No. 11.

SEC. 22 T. 11 R. 17W
NEc SE

Total Depth. 3396' SLM
Comm. 3-4-38. Comp. 3-31-38
Shot or Treated.
Contractor.
Issued. 5-14-38

County. Ellis



CASING:
16 " 58'
10 3/4 " 1130'
7 " 3392' Corr.

Elevation.

Production. Pct. 2792 B.

Figures Indicate Bottom of Formations.

shale	80
shale & shells	360
shells hrd & shale	460
sand	534
shale	590
iron & lime	620
shale	640
iron	645
sand	782
sand & lime	800
red bed & shells	1106
shale	1110
anhydrite	1150
red bed & shells	1216
shale & shells	1460
salt	1510
shale & shells	1690
brkn lime	1714
lime & shale	1945
lime	2111
lime & shale	2272
lime	2445
lime & shale	2653
limo	2683
lime & shale	2732
lime	2755
brkn limo	2828
limo	3009
brkn lime	3048
lime	3095
brkn lime	3148
lime	3373
sh oil 3160-3185	
Top Simpson 3373	
Simpson Fm.	3392
Cored 3380-3394	
Top Arbuckle 3392	
show of oil	

Standardized.
SLM Corr. 3394=3393
Top Simpson 3372 Corr.
Cored - Corrected 3379-3393
Top Arbucklo 3391 Corr.
Arbucklo lime 3396
Total Depth. SLM

RECEIVED
STATE CORPORATION COMMISSION

NOV 19 1965