

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

ELLIS County. Sec. 22 Twp. 11S Rge. 17W (E) (W)

Location as "NE/CNW%SW%" or footage from lines NE/SE/NE

Lease Owner FRANK J. BLACK

Lease Name J. JOHANSEN Well No. 8

Office Address Box 150, McPherson, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 1-3-38 19

Application for plugging filed 10-4-65 19

Application for plugging approved 10-5-65 19

Plugging commenced November, 10, 1965 19

Plugging completed November, 12, 1965 19

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well GILBERT LETKER, VICTORIA, KANSAS

Producing formation Depth to top Bottom Total Depth of Well 3378 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				16"	54'	None
				10-3/4"	1140'	None
				7"	3372'	2698'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged, back with sand to 3360- feet, dumped 5- sacks cement.
Circulated Mud at 550- feet, pumped 30- sacks cement at 450-feet.
Pumped 30- sacks cement at 200-feet, put ten sacks on top.

PLUGGING COMPLETE.

NOV 29 1965
11-19-65

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor LYNCH CASING PULLING, COMPANY. NO. 457

Address R.Rt. 4 GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF MCPHERSON, ss.

Frank J. Black (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 150, McPherson, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of November, 1965

My commission expires July 16, 1967

Jerry Peltzman
JERRY PELTZMAN Notary Public.

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

MAGNOLIA PETROLEUM CO.
J. Johansen No. 8

SEC. 22 T. 11 R. 17W.
NE SE NE

Total Depth. 3378
Comm. 12-5-37. Comp. 1-3-38
Shot or Treated. 2000 gal.
Contractor.
Issued. 2-5-38

County Ellis.

CASING.

16" 54'
103/4" 1140'
7" 3372' SLM



Elevation.

Production. Pot. 2569 B.
after acid.

Figures Indicate Bottom of Formations.

Cellar	7
red bed	110
shale and shells	435
red bed	455
shale and shells	530
lime and shells	625
shale and shells	760
shale & lime shells	1050
shale and lime	1120
Top Anhydrite	1120
anhydrite	1150
shale and shells	1675
shale and lime	2087
lime	2185
lime and shale	2380
shale and shells	2666
lime	2725
shale and lime	2806
broken lime	2850
lime	2985
broken lime	3022
lime	3087
broken lime	3160
show oil	3160
lime	3350
show oil	3235
Top Simpson	3350
Cored	3362' to 3374.
Rec.	10'
Simpson Form	3372
Top Arbuckle	3372
Standardized	
Arbuckle lime	3378
Total Depth.	SLM

RECEIVED
STATE GEOLOGICAL COMMISSION

NOV 19 1965

Test before acid swabbed 496 bbls in 7 hours. swabbing from bottom