


15.051.04369.00.00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ellis County, Sec. 25 Twp. 13 Rge. 18 (E) W (W)

Location as "NE/CNW&SW" or footage from lines SE SE SE  
Lease Owner Clinton Oil Company  
Lease Name Gross "D" Well No. 4  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 9-28-64 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 9-30-64 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted.



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3650 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	226'	None
				5-1/2"	3612'	2986'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3580', sanded hole to 3400' and dumped 4 sacks of cement @ 3400' with dump bailer. Pulled 5 1/2" casing to 600' and circulated pipe with 26 sacks of gel mud. Pulled 5 1/2" casing to 500' and pumped in 20 sacks of cement @ 500'. Pulled 5 1/2" casing to 200' and pumped in 20 sacks of cement. Pulled balance of 5 1/2" casing, checked fluid to 65', mudded to 35' and ran 10 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

OCT 7 1964

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY **CONSERVATION DIVISION**  
Address CHASE, KANSAS Wichita, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.  
NOEL J. KNIGHT (employee of owner) or (~~owner or owner's agent~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of October, 1964

My commission expires May 20, 1968 Milton J. Volin Notary Public.

WELL LOG  
15-051-0-1869-00-00

COMPANY Clinton Oil Co

SEC. 25 T. 13S R. 18W

FARM GROSS

NO. #4-D

LOC. SE SE SE


TOTAL DEPTH 3651'

COUNTY Ellis

COMM. 5-11-64

COMP. 5-20-64

CONTRACTOR Garvey Drilling Company



CASING 8 5/8" @ 226' w/150 sx

5 1/2" @ 3613' w/110 sx

ELEVATION 2067' DS

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

- 20' Surface Clay
- 226' Clay and Blue Shale
- 500' Shale
- 770' Red Bed and Shells
- 960' Sand
- 1115' Shale
- 1303' Shale and Gyp Streaks
- 1342' Anhydrite
- 1675' Shale and Shells
- 1960' Shale and Lime
- 2001' Lime
- 2190' Shale and Lime
- 2570' Lime
- 2712' Lime and Shale
- 3095' Shale and Lime
- 3260' Lime and Shale
- 3651' Lime
- 3651' RTD

Produced Pursuant to Order of the  
State of Kansas

June 7 1964

Notary Public for the State of Kansas  
County of Barton

State of Kansas }  
County of Barton } SS

I, Sam N. Stephens of Garvey Drilling Company  
upon oath state the above and foregoing is a true and correct copy of the log of the Gross #4-D well.

Sam N. Stephens

Subscribed and sworn to before me this 2nd day of June 19 64

My Commission Expires: 23rd September 1967

Howard C. Jensen  
NOTARY PUBLIC