

# WELL RECORD

Company Cities Service Oil Co. Well No. 10 Farm Bemis  
 Location 330' North & 330' East of S/4 Cor. Sec. 21 T. 11 R. 17W  
 Elevation \_\_\_\_\_ County Ellis State Kansas  
 Drlg. Comm. August 3, 1937 Contractor J. E. Mabee Drilling Company  
 Drlg. Comp. September 1, 1937 Acid None  
 T. D. 3384' Initial Prod. 2025 oil, no water, 2 1/2 hrs.

CASING RECORD:

15-1/2" @ 106' cem. 85 sx  
 10-3/4" @ 1111' cem. 460 sx  
 7" @ 3374' cem. 265 sx

FORMATION RECORD:

shale & shells 628  
 shale, shells & red bed 1053  
 red bed & shale 1097  
 anhydrite 1112  
 shale & shells 1205  
 lime & shale 1280  
 shale & shells 1405  
 shale & lime 2137  
 lime 2177  
 lime & shale 2947  
 lime 3060  
 lime & shale 3153  
 lime 3217  
 lime & shale 3374  
 lime 3376  
 SLM Corr. 3376 = 3378  
 lime 3384 TD

Top Simpson (Sh. Dol. Ls.) 3358'  
 Top Sand 3372'  
 Corr. Top Siliceous 3376'  
 Penetration 8'  
 Total Depth 3384'

Filled up 1100' in 30 mins.  
 1400' in 50 mins.  
 2700' in 2 1/2 hrs.

SYFO: 800' 1/2°  
 1500' OK  
 2000' OK  
 2500' 0°

**PLUGGING**  
 FILE SEC 21 T 11 R 17W  
 BOOK PAGE 17 LINE 9