

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-051-24,613-00-00 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Petroleum, Inc. OPERATOR'S LICENSE NO. 5238

ADDRESS 301 N. Main, Suite 900, Wichita, KS 67202 PHONE # (316) 291-8281

LEASE (FARM) Amrein WELL NO. 2 WELL LOCATION E/2 SW/4 SW/4 COUNTY Ellis

SEC. 6 TWP. 13S RGE. 19 (~~E) or (W)~~ TOTAL DEPTH 3930' PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 246' CEMENTED WITH 160 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Circulate heavy mud in hole. 1st plug at 3875'-20 sx. 2nd

plug at 1540'-20 sx. 3rd plug at 770'-100 sz. 4th plug at 300'-40 sx. 5th plug at 40' SB-

10 sx. Rathole-15 sx. All cement 60/40 pozmix, 6% gel, 2 sx. Flocel

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? No

(If not explain.) Sent to operator for completion

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN at 5:30 a.m. on 10-17-89

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Maley PHONE # (913) 674-5768

ADDRESS 216E. McFarland, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack E. Wharton
(Operator or Agent)

DATE: 10-23-89

OCT 24 1989
10-24-1989
STATE CORPORATION COMMISSION
Wichita, Kansas