



GEORGE DOCKING Governor
 MARION BEATTY Chairman
 HARRY G. WILES Commissioner
 RICHARD C. BYRD Commissioner
 RAYMOND B. HARVEY Secretary
 CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 29 1959
 CONSERVATION DIVISION
 Wichita, Kansas

Jewel M. Ogden, Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date 6-23-59, 19 , authorized the following plugging operation:

Operator's Full Name: Sterling Drg Co

Complete Address: Sterling, Kans

Lease Name: Bemis Well No. 1

Location: NW NE NW Sec. 29 Twp. 13 Rge. 19 (E) (W)

County: Ellis Total Depth: 3870

Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

8 5/8" at 200', circulated with cement .

Circulate hole with heavy mud, set cementing plug at 600', displace

20 sax cement through drill pipe, heavy mud to 180', set plug and 15 sax

cement, heavy mud to 40', set cementing plug, 1/2 sack hulls and 10 sax

cement to bottom cellar.

Very truly yours,

Signed: *Jedon Letty*
 Conservation Division Agent