



15-007-21067-0000

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

January 13, 1981

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Jack Kaiser of Trans-Pac Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Wild Boy's Land-Cattle and Oil Company

Complete Address: Suite 3A, 809 North Waco, Wichita, Kansas 67202

Lease Name: Schrock Well No. 1

Location: SE NE ANBRCC Sec. 10 Twp. 35 Rge. 10 (W)

County: Barber Total Depth: 5375'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Kaiser was instructed to plug the well as follows:

8 5/8" - 325' - 275 sacks circ. Fill hole with mud. Pump 70 sacks (50-50 Pozmix w/4% gel) cement through drill pipe at 400'. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Cement rat hole with 5 sacks cement. Cement mouse hole with 5 sacks cement.

Very truly yours,

01-19-81
JAN 19 1981

William J. Lomen
Conservation Division Agent