



15051-22788-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Leroy Hunt of Montgomery Exploration has this date requested permission to plug the following described well:

Operator's Full Name: Montgomery Drilling Program

Complete Address: P.O. Box 1114 Hays, Ks. 67601

Lease Name: Peifer Well No. 1

Location: SW SE NE Sec. 22 Twp. 13 Rge. 19 (E) (W)

County: Ellis Total Depth: 3725'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXXX

Other well as hereafter indicated:

Mr. Hunt was instructed to plug the well as follows:

8 5/8"- S.P. 265' cuc. w/165 sacks common-2% Gel.-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. & 8 5/8" plug.

Spot w/drill stem w/heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 250' w/40 sacks cement

3rd plug-solid bridge of hulls & plug @ 40' w/10 sacks cement.

Circulate 10 sacks in rat hole.

Very truly yours,

[Signature]
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

MAR 22 1982

Conservation Division
Wichita, Kansas