

69

State of Kansas



15:05:170108:00:00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
AUG 21 1967  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Miller of L. J. Dreiling & Sons, Inc. has this date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: H. B. Mabee Company

Complete Address: Box 94718, Oklahoma City, Oklahoma

Lease Name: Meis Well No. 1

Location: NW NW NE Sec. 22 Twp. 13 Rge. 19 (E)(W) X

County Ellis Total Depth 3740' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Miller was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 680' and displace  
100 sc cement thru drill pipe, Heavy mud to 150' set cementing plug and  
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with  
2 sc cement.

Very truly yours,

Ray F. Massey  
Conservation Division Agent