



15-051-22634-01-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Leroy Hunt of Montgomery Drilling has this
Program
date requested permission to plug the following described well:

Operator's Full Name: Montgomery Explorations Company

Complete Address: P. O. Box 1114, Hays, Kansas 67601

Lease Name: Pfeifer Well No. #1

Location: SE Sec. 22 Twp. 13 Rge. 19 (E) (W)

County: Ellis Total Depth: 3710

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated:

Mr. Leroy Hunt was instructed to plug the well as follows:

8 5/8"-234' sp. cuc. w/175 sacks common-2% Gel.-3% Cal. Cl.

Ordered 125 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem with heavy mud between all plugs.

1st plug @ 780' w/70 sacks cement

2nd plug @ 210' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement.

5 sacks of cement in rat hole.

Very truly yours,

RECEIVED
STATE CORPORATION COMMISSION

OCT 2 1981

Gilbert J. Loh
Conservation Division Agent

CONSERVATION DIVISION
Wichita Kansas