

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Ellis County. Sec. 1 Twp. 13 Rge. 20 (E) (W)

Location as "NE/CNW/SW" or footage from lines. NW NW SE

Lease Owner National Cooperative Refinery Association

Lease Name Flax Well No. 1

Office Address 820 Union National Bank Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 5, 1953

Application for plugging filed June 9, 1953

Application for plugging approved June 8, 1953


Plugging commenced June 5, 1953

Plugging completed June 5, 1953

Reason for abandonment of well or producing formation Not capable of producing.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3921 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	139'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded hole to 130', set plug, dumped 15 sacks cement + 1/2 Sack hulls. Mudded hole to 40'. Set plug, dumped 1/2 sack hulls + 10 sacks cement on up to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn R. Nye Drilling Company

Address Hays, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.

C. R. Sears (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Sears

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 15 day of June, 19 53

My commission expires June 30, 1954.

C. Orville May  
Notary Public.

**PLUGGING**  
FILE SEC 1 T 13 R 20W  
BOOK PAGE 106 LINE 26

06-16-53  
SION

Company: National Cooperative Refinery Association  
 Contractor: Glenn R. Nye Drilling Company  
 Commenced: May 22, 1953  
 Completed: June 5, 1953

15051001850000

Farm: Flax #1  
 Location: NW NW SE Sec. 1-13-20  
 Ellis County, Kansas  
 Casing Record: 8 5/8" set at 139'  
 Dry and Abandoned

(figures below indicate bottoms)

post rock	25	
gravel & sand	70	
sand & shale	90	
blue shale	141	
shale	330	
blue shale	535	
shale & sand	840	
shale & sand & salt	880	
red bed & shale	1025	
sand	1155	
shale	1490	
anhydrite	1495	
anhydrite	1537	
red bed & shale	1780	
red bed & shale	1990	
shale & shells	2080	
shale & lime streaks	2210	
lime & shale	2345	
lime & shale	2475	
lime & shale	2560	
lime & shale	2580	
shale & lime	2650	
lime & shale	2785	
lime & shale	2890	
lime & shale	3002	
lime & shale	3115	
lime & shale	3223	Topeka 3208 (-1043)
lime & shale	3291	
lime & shale	3330	
lime & shale	3370	Elevation 2162 D.F.
lime & shale	3416	
lime & shale	3460	Heebner 3444 (-1279)
lime & shale	3510	Lansing 3484
lime	3550	
lime & shale	3571	
lime & shale	3580	
lime	3625	
lime	3665	
lime & shale	3689	
lime	3705	
lime	3750	
lime, shale & marm.	3790	
marm. chert & sand	3820	
chert	3828	
chert	3852	
cherty cong.	3855	
chert & lime	3875	
cong. & arbuckle	3902	Arbuckle 3897 (-1732)
arbuckle	3921	T. D. (-1756)

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

GLENN R. NYE DRILLING COMPANY

By Glenn R. Nye

STATE OF KANSAS )  
 ELLIS COUNTY )

SS

**PLUGGING**  
 FILE SEC 1 T 13 R 2014  
 BOOK PAGE 106 LINE 26

Subscribed to and sworn to before me, a notary public, in and for said County and State this 19th day of June, 1953.

John L. Spiess  
 Notary Public

My Commission Expires May 9, 1957